Temple at the Nielson Site

Supplemental Geotechnical Engineering Services Report

March 28, 2023 | Terracon Project No. 26235004

Prepared for:

The Haskell Company 111 Riverside Avenue Jacksonville, Florida 32202





2110 Overland Avenue, Suite 124
Billings, Montana 59102
P (406) 656-3072
Terracon.com

March 28, 2023

The Haskell Company 111 Riverside Avenue Jacksonville, Florida 32202

Attn: Mr. Aaron Arbuckle, Design Manager

P: (801) 647-6808

E: Aaron.arbuckle@haskell.com

Re: Supplemental Geotechnical Engineering Services Report

Temple at the Nielson Site

Skyline Drive Cody, Wyoming

Terracon Project No. 26235004

Dear Mr. Arbuckle:

We have completed the scope of Supplemental Geotechnical Engineering Services for the above referenced project in general accordance with the Supplemental Change Order No. 2 – Geotechnical Engineering Services proposal dated January 26, 2023. The approved scope was initiated with a signed Professional Services Agreement Modification No. 001 to Haskell Contract No. 201-006 dated January 31, 2023. This report presents the findings of the supplemental subsurface exploration and provides geotechnical recommendations concerning earthwork and the design and construction of foundations, floor slabs, and pavements. Parameters are provided for use by others in design of a retaining wall along the north side of the proposed project.

We appreciate the opportunity to be of service to you on this project. If you have any questions concerning this report or if we may be of further service, please contact us.

Sincerely,

Terracon

Matthew D. Hoffmann, P.E. Office Manager

Gary Rome, P.E. Senior Engineer

Temple at the Nielson Site | Cody, Wyoming March 28, 2023 | Terracon Project No. 26235004



Table of Contents

Introduction	
Project Description	
Site Conditions	3
Geotechnical Characterization	5
Seismic Site Class	6
Percolation/Infiltration	7
Corrosivity	8
Geotechnical Overview	9
Earthwork	10
Site Preparation	10
Excavation	11
Fill Material Types	11
Fill Placement and Compaction Requirements	14
Utility Trench Backfill	15
Grading and Drainage	15
Earthwork Construction Considerations	16
Construction Observation and Testing	16
Shallow Foundations	17
Design Parameters - Compressive Loads	17
Foundation Construction Considerations	18
Floor Slabs	19
Floor Slab Design Parameters	19
Floor Slab Construction Considerations	20
Below-Grade Structures	21
Lateral Earth Pressures	21
Design Parameters	22
Subsurface Drainage for Below-Grade Walls	23
Pavements	24
General Pavement Comments	24
Pavement Design Parameters	24
Pavement Subgrade Preparation	25
Pavement Section Thicknesses	
Pavement Drainage	27
Pavement Maintenance	
Frost Considerations	28
General Comments	29

Figures

GeoModel

Temple at the Nielson Site | Cody, Wyoming March 28, 2023 | Terracon Project No. 26235004



Attachments

Exploration and Testing Procedures
Photography Log
Site Location and Exploration Plans
Exploration and Laboratory Results
Supporting Information

Note: This report was originally delivered in a web-based format. **Blue Bold** text in the report indicates a referenced section heading. The PDF version also includes hyperlinks which direct the reader to that section and clicking on the **perfection** logo will bring you back to this page. For more interactive features, please view your project online at **client.terracon.com**.

Refer to each individual Attachment for a listing of contents.

Temple at the Nielson Site | Cody, Wyoming March 28, 2023 | Terracon Project No. 26235004



Introduction

This report presents the results of our subsurface exploration and Supplemental Geotechnical Engineering Services performed for the proposed new Temple at the Nielson Site to be located at Skyline Drive in Cody, Wyoming. The purpose of these services was to provide information and geotechnical engineering recommendations relative to:

- Subsurface soil and rock conditions
- Groundwater conditions
- Seismic site classification per IBC
- Site preparation and earthwork
- Foundation design and construction
- Floor slab design and construction
- Lateral earth pressures
- Pavement design and construction
- Stormwater pond considerations (infiltration data)
- Frost considerations

The geotechnical engineering Scope of Services for this project included the advancement of test borings, laboratory testing, engineering analysis, and preparation of this report.

Drawings showing the site and boring locations are shown on the **Site Location** and **Exploration Plan**, respectively. The results of the laboratory testing performed on soil samples obtained from the site during our field exploration are included on the boring logs and as separate graphs in the **Exploration Results** section.

Project Description

Our initial understanding of the project was provided in our supplemental geotechnical engineering services change order proposal and was discussed during project planning. A period of collaboration has transpired since the project was initiated, and our final understanding of the project conditions is as follows:

The preliminary site layout provided by Haskell was located approximately in the same area as the Concept G layout previously provided by DJ&A. The primary change was the inclusion of a planned retaining wall along the northern portion of the parking lot adjacent to the property boundary. This retaining structure is near an area of past slope movement where a deep boring was performed in 2022 to assess slope stability. The

Temple at the Nielson Site | Cody, Wyoming March 28, 2023 | Terracon Project No. 26235004



global stability of the slope was found to be generally stable without structural loading added to the area, and a setback of 30 feet was recommended. With planned retaining wall development at this area to allow for paving up to this feature, additional subsurface information along the retaining wall alignment was necessary.

Item	Description		
Information Provided	Terracon performed a previous geotechnical evaluation and provided a report for the site, Terracon Report No. 26225020, in August 2022. Terracon was requested in November 2022 to develop a proposal to provide supplemental borings for a proposed retaining wall along the north boundary by our client (DJ&A) for the initial geotechnical scope. As the project advanced, we were approached by Haskell (the current engineer for the project) to provide additional supplemental borings (five building borings and five pavement borings) to those proposed for the retaining wall work and updated geotechnical recommendations in an email dated December 9, 2022 from Mr. Arbuckle. At that time, we were provided a supplemental boring layout. On January 17, 2023 we were provided with another updated layout (Drawing C-121-Preliminary Site Plan_geotech markups) showing the desired supplemental boring locations and an additional five infiltration test locations to be added to the scope.		
Project Description	We understand the project is to include the construction of a Temple site for the Church of Jesus Christ of Latter-day Saints along with associated parking and landscaping at the site. The development will include auxiliary and utility buildings located on the property as well.		
Proposed Structures	It is assumed that the proposed Temple with an approximate footprint on the order of 40,000 square feet is to be a multistory wood-framed, or light gauge steel construction with brick/masonry veneer. Shallow, frost-depth footings, stem wall, and slab-on-grade construction is assumed for a majority of the building. A basement level will be included in the middle of the building.		
Finished Floor Elevation	Not provided at the time of report preparation; however, assumed to be within approximately 2 to 4 feet of existing site grade.		
Maximum Loads (assumed)	 Wall loads - 4,500 to 7,500 pounds per lineal foot (pfl) Column loads - 75 to 200 kips Slab loads - 250 pounds per square foot (psf) 		

Temple at the Nielson Site | Cody, Wyoming March 28, 2023 | Terracon Project No. 26235004



Description		
Based on topographic data, it appears that minor grading on the order of 2 to 4 feet will be required to develop final grade at the site. Final slope angles of as steep as 5H:1V (Horizontal: Vertical) surrounding pavement and structures are expected.		
Anticipated basement level on the order of 15 to 20 feet below finished grade.		
Site grading to require a small retaining wall along north property boundary, approximately 200 feet long. Total height of the wall is anticipated to be less than 5 feet exposed.		
the wall is anticipated to be less than 5 feet exposed. Paved driveway and parking will be constructed on approximately 1.5 acres of the Temple Area of the parcel. We anticipate that the pavement will generally support passenger vehicles with periodic service trucks. Based on The Church's requirements for new construction of parking lots, we assume the following traffic loading: Parking: Six 18-kip ESALs per week Driveways: Fifteen 18-kip ESALs per week Trash Enclosure Approach Slab: One 40-kip axle load per week Traffic Analysis Period: Asphaltic Concrete Pavement: 40 years		
IBC 2021		
0 5 1 t 1 a 1 1 1		

Terracon should be notified if any of the above information is inconsistent with the planned construction, especially the grading limits, as modifications to our recommendations may be necessary.

Site Conditions

The following description of site conditions is derived from our site visit in association with the field exploration and our review of publicly available geologic and topographic maps.


Item	Description
Parcel	The project is located north of the intersection of Skyline Drive with the Cody Canal in Cody, Wyoming.
Information	Approximate GPS Coordinates: 44.5119 °N, 109.0819° W
	See Site Location

Temple at the Nielson Site | Cody, Wyoming March 28, 2023 | Terracon Project No. 26235004



Item	Description	
Existing Improvements	Undeveloped land	
Current Ground Cover	Native grasses and isolated areas of bare soil	
Existing Topography	The site is situated on a bluff or terrace area with a slight slope along the top of the bluff from south, near Elevation 5142 feet above mean sea level (MSL), toward the north-northeast with a maximum drop of approximately 7 feet based on site specific topographic survey information provided by DJ&A. The north and west sides of the parcel are elevated above low-lying drainage areas feeding Sulfur Creek to the north of the site. The bluff is situated approximately 45 to 90 feet above the low-lying areas to the west and north.	





We also collected photographs at the time of our field exploration program. Representative photos are provided in our **Photography Log**.

Geotechnical Characterization

We have developed a general characterization of the subsurface conditions based upon our review of the subsurface exploration, laboratory data, geologic setting and our understanding of the project. This characterization, termed GeoModel, forms the basis of our geotechnical calculations and evaluation of the site. Conditions observed at each exploration point are indicated on the individual logs. The individual logs can be found in

Temple at the Nielson Site | Cody, Wyoming March 28, 2023 | Terracon Project No. 26235004



the **Exploration Results** and the GeoModel can be found in the **Figures** attachment of this report.

As part of our analyses, we identified the following model layers within the subsurface profile. For a more detailed view of the model layer depths at each boring location, refer to the GeoModel.

Model Layer	Layer Name	General Description
1	Upper Gravel	Well-Graded GRAVEL with Silt and Sand OR Silty Gravel with Sand, fine grained, subangular, light brown, dry, medium dense
2	Lower Gravel	Poorly-Graded GRAVEL with Silt and Sand, coarse grained, subrounded, light brown to gray, dry, medium dense to very dense, some cobbles
3	Clay	Sandy Fat CLAY, medium to high plasticity, brown, moist, stiff to very stiff
4	Bedrock	CLAYSTONE, tan, moist, fine-grained, moderately fractured, thin bedding, highly weathered, weak rock, interbedded sandstone layer

The borings were advanced in the dry using an air rotary drilling technique that allows short term groundwater observations to be made while drilling. Groundwater seepage was not encountered within the maximum drilling depth at the time of our field exploration, which was conducted in February 2023. Groundwater conditions may be different at the time of construction. Groundwater conditions may change because of seasonal variations in rainfall, runoff, and other conditions not apparent at the time of drilling. Long-term groundwater monitoring was outside the scope of services for this project.

Seismic Site Class

The seismic design requirements for buildings and other structures are based on Seismic Design Category. Site Classification is required to determine the Seismic Design Category for a structure. The Site Classification is based on the upper 100 feet of the site profile defined by a weighted average value of either shear wave velocity, standard penetration resistance, or undrained shear strength in accordance with Section 20.4 of ASCE 7 and the International Building Code (IBC). Based on the soil/bedrock properties observed at the site and as described on the exploration logs and results, our professional opinion is for that a **Seismic Site Classification of C** be considered for the project. Subsurface explorations at this site were extended to a maximum depth of 41.5 feet. The site properties below the boring depth to 100 feet were estimated based on our

Temple at the Nielson Site | Cody, Wyoming March 28, 2023 | Terracon Project No. 26235004



experience and knowledge of geologic conditions of the general area. Additional deeper borings or geophysical testing may be performed to confirm the conditions below the current boring depth.

Percolation/Infiltration

Terracon performed the infiltration testing on February 13, 2023. The infiltration testing was performed in general accordance with the City of Cody Public Works requirements at five locations as directed by Haskell. Preparation of the infiltration test was begun by drilling a hole to the depth of approximately 10 feet per the direction of Haskell civil design team using 10" outside diameter hollow stem augers at the locations shown as I-1 through I-5 on the attached Exploration Plan. Two inches of gravel was placed at the bottom of the hole then a perforated PVC pipe (ten feet in length and four inches in diameter) was placed inside the hollow stem augers. The exterior of the PVC pipe was filled with coarse gravel prior to the removal of the hollow stem augers. Eighteen inches of water was added inside the PVC pipe for the soaking period, which generally percolated within 20 minutes at all locations. A second 18 inches was then placed in each percolation hole, and again the water percolated out of the location within approximately 20 minutes or less. The testing then began with 12 inches of water placed in the holes and due to the speed of infiltration, readings were taken at 30-second intervals to obtain the data. This was conducted three separate times in each hole to develop the test rates provided in the table below:

Table 1: Infiltration Rate Summary Table

Location	Depth (feet)	Material Encountered	Test Rate (min/in)
I-1	10	Poorly-Graded Gravel with Silt and Sand (GP-GM)	1.0
I-2	10	Poorly-Graded Gravel with Silt and Sand (GP-GM)	0.5
I-3	10	Poorly-Graded Gravel with Silt and Sand (GP-GM)	1.3
I-4	10	Poorly-Graded Gravel with Silt and Sand (GP-GM)	1.0
I-5	10	Poorly-Graded Gravel with Silt and Sand (GP-GM)	0.5

A design rate should be selected by the designer by applying an appropriate factor of safety to the field infiltration rate presented above. With time, the bottoms of infiltration systems tend to clog with organics, sediments, and other debris. Long-term maintenance will be required to help reduce clogging and maintain the designed infiltration rate of the systems. The infiltration rate may have been affected by the following factors, which should be considered when selecting the factor of safety:

Temple at the Nielson Site | Cody, Wyoming March 28, 2023 | Terracon Project No. 26235004



- The infiltration test was conducted in a 10-inch diameter borehole. The infiltration rates in large storm water infiltration systems may be different than the infiltration rate measured in the relatively small 10″ borehole.
- The infiltration test was conducted using relatively clean water. However, the storm water will likely not be clean and may contain organics, fines, and contaminations. The presence of these materials will tend to decrease the rate that the water will percolate from the infiltration systems. The design of the stormwater infiltration systems should account for the water quality and should incorporate structures/devices to remove these materials in the water.

Based on the soils encountered during our exploration, we expect the infiltration rates of the soils to vary between multiple areas due to the variations in the soil types. Infiltration into the soils with a higher percentage of fines would be expected to have slower infiltration rates. The design elevations and sizes of the proposed infiltration systems should account for this expected variability in the infiltration rate.

Corrosivity

The table below lists the results of laboratory soluble sulfate, electrical resistivity, and pH testing for a select sample of native soils that would be within the potential backfill/retained zone of the retaining wall planned for the north side of the site. The values may be used to estimate potential corrosive characteristics of the on-site soils with respect to contact with the various underground materials which will be used for project construction.

Corrosivity Test Results Summary

Boring	Sample Depth (feet)	Soil Description	Soluble Sulfate (%)	Electrical Resistivity (Ω-cm)	рН
RW-3	2.5-4.0	Silty Gravel with Sand (GM)	0.109	407	7.5

Results of soluble sulfate testing can be classified in accordance with ACI 318 – Building Code Requirements for Structural Concrete. Numerous sources are available to characterize corrosion potential to buried metals using the parameters above. ANSI/AWWA is commonly used for ductile iron, while threshold values for evaluating the effect on steel can be specific to the buried feature (e.g., piling, culverts, welded wire reinforcement, etc.) or agency for which the work is performed. Imported fill materials may have significantly different properties than the site materials noted above and should be evaluated if expected to be in contact with metals used for construction.

Temple at the Nielson Site | Cody, Wyoming March 28, 2023 | Terracon Project No. 26235004



Consultation with a NACE certified corrosion professional is recommended for buried metals on the site.

Geotechnical Overview

A supplemental geotechnical exploration has been performed for the proposed new Temple at the Nielson Site in Cody, Wyoming. A total of 14 borings were drilled to depths ranging between 10.4 to 11.5 feet below existing grade for pavements, 18.0 to 41.5 feet below existing grade for the building, and 21.5 feet below existing grade for evaluation of the retaining wall foundation area on the north portion of the site. This report addresses the geotechnical recommendations for foundations along with earthwork portions and pavement construction for the project.

The site appears suitable for the proposed construction based upon geotechnical conditions encountered in the test borings, provided that the recommendations provided in this report are implemented in the design and construction phases of this project.

The predominant subsurface materials are gravel soils with varying amounts of fines along with isolated zones of medium to high plasticity sandy fat clay in the upper 8.0 feet of the profile on the south side of the property, along the planned new access road/cul-de-sac. The soil profiles are presented in further detail on the attached GeoModel, which can be found in the **Figures** section of the report, along with on the individual Boring Logs within the **Exploration Results** section of this report. Groundwater was not encountered within the maximum depths of exploration during or at the completion of drilling.

Based on the conditions encountered and estimated load-settlement relationships, the proposed structures can be supported on conventional continuous or spread footings bearing on properly prepared native gravel soils.

The near surface soils consist primarily of gravels, with an area of lean clay with gravel located along the eastern portion of the site. The gravel soils are expected to provide stable subgrade conditions for construction of planned improvements. The clay soils, where encountered, could become unstable with typical earthwork and construction traffic, especially after precipitation events. The establishment of effective drainage should be completed early in the construction sequence and maintained after construction to avoid potential issues. If possible, the grading should be performed during the warmer and drier times of the year. If grading is performed during the winter months, an increased risk for possible undercutting and replacement of unstable subgrade will persist. Additional site preparation recommendations, including subgrade improvement and fill placement, are provided in the **Earthwork** section.

The soils which form the bearing stratum for shallow foundations are medium dense to very dense alluvial terrace gravel deposits, which provide reliable support with limited

Temple at the Nielson Site | Cody, Wyoming March 28, 2023 | Terracon Project No. 26235004



potential for differential settlement when properly prepared. The **Shallow Foundations** section addresses support of the building bearing on properly prepared native granular soils. The **Floor Slabs** section addresses slab-on-grade support of the building.

Our opinion of pavement section thickness design has been developed based on our understanding of the intended use, assumed traffic, and subgrade preparation recommended herein using methodology contained in the 1993 Guideline for Design of Pavement Structures by the American Association of State Highway and Transportation Officials (AASHTO-1993) and adjusted with consideration to local practice. The Pavements section includes minimum pavement component thickness.

Based on our previous study conducted at the site, past slope instabilities appear to have occurred at the northern portion of the site. An obvious past slope failure lobe, generally moving in the direction of Sulfur Creek from the bluff site, was noted in this review, and supplemental borings were placed along the proposed alignment of a retaining wall at this location. Based on subsurface conditions encountered consisting of medium dense to very dense gravel deposits overlying interbedded claystone and sandstone bedrock, global stability of the slope is not of concern. The retaining wall design to be completed by Haskell should include parameters as provided in the **Below-Grade Structures** and **Lateral Earth Pressures** sections of this report.

The recommendations contained in this report are based upon the results of field and laboratory testing (presented in the **Exploration Results**), engineering analyses, and our current understanding of the proposed project. The **General Comments** section provides an understanding of the report limitations.

Earthwork

Earthwork is anticipated to include clearing and grubbing, excavations, and fill placement. The following sections provide recommendations for use in the preparation of specifications for the work. Recommendations include critical quality criteria, as necessary, to render the site in the state considered in our geotechnical engineering evaluation for foundations, floor slabs, and pavements.

Site Preparation

Prior to placing fill, existing vegetation, root mat, and existing fill should be removed. Complete stripping of these materials should be performed in the proposed building and parking/driveway areas.

For foundations, excavations should be conducted to base of footing elevation, at which elevation native gravel subgrade should be moisture conditioned and compacted to a

Temple at the Nielson Site | Cody, Wyoming March 28, 2023 | Terracon Project No. 26235004



minimum of 98 percent of the maximum laboratory dry density per ASTM D698 prior to placement of foundation concrete.

After removal of vegetation and any unsuitable materials, the pavement subgrade areas should be scarified to a depth of 12 inches and recompacted to 95 percent of the maximum dry density per ASTM D698 to improve loose or soft areas. After scarifying and re-compacting, the pavement subgrade should be subsequently proofrolled with an adequately loaded vehicle such as a fully-loaded tandem-axle dump truck with a minimum weight of 20 tons and tire pressures on the order of 90 psi. The proofrolling should be performed under the direction of the Geotechnical Engineer. Areas excessively deflecting, yielding, pumping, or rutting under the proofroll should be delineated and subsequently addressed by the Geotechnical Engineer. Excessively wet or dry material should either be removed or moisture conditioned and recompacted.

Where fill is placed on existing slopes steeper than 5H:1V, benches should be cut into the existing slopes prior to fill placement. The benches should have a minimum vertical face height of 1 foot and a maximum vertical face height of 3 feet and should be cut wide enough to accommodate the compaction equipment. This benching will help provide a positive bond between the fill and natural soils and reduce the possibility of failure along the fill/natural soil interface.

Interior slabs-on-grade should be prepared in accordance with the **Floor Slabs** section recommendations subsequently discussed within this report. Exterior slabs-on-grade (flatwork) should be prepared consistent with pavement subgrade as discussed above.

Excavation

We anticipate that excavations for the proposed construction can be accomplished with conventional earthmoving equipment. The bottom of excavations should be thoroughly cleaned of loose soils and disturbed materials prior to backfill placement and/or construction.

Fill Material Types

Fill required to achieve design grade should be classified as Structural Fill, Select Fill, and General Fill. Structural Fill (if required) is material used below foundations, or within 5 feet horizontally of structures, or pavements. Select Fill is optional material for use from native prepared subgrade to within 6 inches of base of interior floor slabs, where the use of Structural Fill gradations is not strictly required. General fill is material used to achieve grade outside of these areas. Earthen materials used for structural and general fill should meet the following material property requirements:

Temple at the Nielson Site | Cody, Wyoming March 28, 2023 | Terracon Project No. 26235004



Reuse of On-Site Soil: Excavated on-site granular soil may be selectively reused as fill below pavement and landscaping areas, and as exterior backfill of foundations. The on-site fat clay soils are not recommended for reuse on site due to the potential difficulties in moisture conditioning and compacting these materials which are sensitive to moisture conditions.

Material property requirements for on-site soil for use as general fill and Structural Fill are noted in the table below:

Property	General Fill	Structural Fill
Composition	Free of deleterious material	Free of deleterious material
Maximum particle size	6 inches (or 2/3 of the lift thickness)	3 inches
Fines content	Not limited	Less than 12% Passing No. 200 sieve
Plasticity	Not limited	Maximum plasticity index of 10
GeoModel Layer Expected to be Suitable ¹	1, 2	1, 2

1. Based on subsurface exploration. Actual material suitability should be determined in the field at time of construction.

Imported Fill Materials: Imported fill materials should meet the following material property requirements. Regardless of its source, compacted fill should consist of approved materials that are free of organic matter and debris. Frozen material should not be used, and fill should not be placed on a frozen subgrade.

Soil Type ¹	USCS Classification	Acceptable Parameters (for Structural Fill)
Structural Fill ² (imported material)	GW, GP, SW, SP, and dual (GM/SM) symbols	Below foundation elevation, below slab areas, and as replacement backfill
Select Fill ³ (sub-slab areas above footing elevation)	GW, GP, SW, SP and dual (GM/SM) symbols	Below slab areas, interior utility trench backfill, above foundation/footing elevation (option to replacement using Structural Fill)

Temple at the Nielson Site | Cody, Wyoming March 28, 2023 | Terracon Project No. 26235004



Soil Type ¹	USCS Classification	Acceptable Parameters (for Structural Fill)
Crushed Base Course	1 ½ inch minus, Wyoming Public Works Standard Specifications (WPWSS) Section 02190, Grading W	Leveling course below slab above Structural or Select Fill, and as crushed aggregate base course for pavements
General Fill ⁴	ML, CL, CL-ML, SM, SP	The on-site gravels and lean clay with gravel soils appear suitable for use as General Fill, including site grade raising material, site (exterior) utility trench backfill, and exterior backfill of foundations.
Non-Frost Susceptible Fill (NFS) ⁵	GP, GW, SP, SW	Below exterior flatwork critical to project to mitigate frost-action

- 1. Structural, Select, and General Fill should consist of approved materials free of organic matter and debris. Frozen material should not be used, and fill should not be placed on a frozen subgrade. A sample of each material type should be submitted to the Geotechnical Engineer for evaluation prior to use on this site.
- 2. Structural Fill, defined as imported aggregate, should meet the following criteria outlined below:

<u>Gradation</u>	Percent Finer By Weigh (ASTM C136)
1 1/2"	100
No. 4	30-60
No. 200 12 (max)	
Liquid Limit	
Plastic Index	10 (max)

3. Select Fill, defined as imported aggregate, should meet the following criteria outlined below:

Gradation	Percent Finer By Weigh (ASTM C136)
3"	100
No. 4	80
No. 40	35
No. 200 15 (max)	
Liquid Limit	30 (max)
Plastic Index	10 (max)

- 4. Significant moisture conditioning of the native clay may be necessary to meet compaction requirements; this will require mechanical reduction in clay clod size (i.e. disking, etc.) to a maximum 1-inch dimension to facilitate moisture conditioning; the necessary moisture adjustment will be difficult during wet/cold seasons.
- 5. Non-Frost Susceptible Fill should have no more than 5 percent passing the No. 200 sieve

Temple at the Nielson Site | Cody, Wyoming March 28, 2023 | Terracon Project No. 26235004



Fill Placement and Compaction Requirements

Structural and general fill should meet the following compaction requirements.

Item	Structural Fill	Select Fill	General Fill
Maximum Lift Thickness	9 inches or less in loose thickness when heavy, self- propelled compaction equipment is used 4 to 6 inches in loose thickness when hand-guided equipment (i.e. jumping jack or plate compactor) is used	Same as Structural Fill	Same as Structural Fill
98% of max. below foundations, interior floor slabs, and interior backfill (including building utility trench backfill) Minimum Compaction Requirements 1,2 City Street requirements change to 95% of max. as determined by modified Proctor test (AASHTO T180) for base course and 90% for subbase course		98% of max. below floor slabs	92% of max. in green areas
Low plasticity cohesive: -2% to +3% of optimum Range Granular: -3% to +3% of optimum		Granular: - 3% to +3% of optimum	As required to achieve min. compaction requirements

- 1. Maximum density and optimum water content as determined by the standard Proctor test (ASTM D 698).
- 2. If the granular material is a coarse sand or gravel, or of a uniform size, or has a low fines content, compaction comparison to relative density may be more appropriate. In this case, granular materials should be compacted to at least 70% relative density (ASTM D 4253 and D 4254). Materials not amenable to density testing should be placed and compacted to a stable condition observed by the Geotechnical Engineer or representative.

Temple at the Nielson Site | Cody, Wyoming March 28, 2023 | Terracon Project No. 26235004



Utility Trench Backfill

Any soft or unsuitable materials encountered at the bottom of utility trench excavations should be removed and replaced with Structural Fill or bedding material in accordance with public works specifications for the utility be supported. This recommendation is particularly applicable to utility work requiring grade control and/or in areas where subsequent grade raising could cause settlement in the subgrade supporting the utility. Trench excavation should not be conducted below a downward 1H:1V (Horizontal: Vertical) projection from existing foundations without engineering review of shoring requirements and geotechnical observation during construction.

On-site materials are considered suitable for backfill of utility and pipe trenches from 1 foot above the top of the pipe to the final ground surface, provided the material is free of organic matter and deleterious substances.

Trench backfill should be mechanically placed and compacted as discussed earlier in this report. Compaction of initial lifts should be accomplished with hand-operated tampers or other lightweight compactors. Where trenches are placed beneath slabs or footings, the backfill should satisfy the gradation requirements of engineered fill discussed in this report. Flooding or jetting for placement and compaction of backfill is not recommended.

Grading and Drainage

All grades must provide effective drainage away from the building during and after construction and should be maintained throughout the life of the structure. Water retained next to the building can result in soil movements greater than those discussed in this report. Greater movements can result in unacceptable differential floor slab and/or foundation movements, cracked slabs and walls, and roof leaks. The roof should have gutters/drains with downspouts that discharge onto splash blocks at a distance of at least 10 feet from the building.

Exposed ground should be sloped and maintained at a minimum 5% away from the building for at least 10 feet beyond the perimeter of the building. Locally, flatter grades may be necessary to transition ADA access requirements for flatwork. After building construction and landscaping have been completed, final grades should be verified to document effective drainage has been achieved. Grades around the structure should also be periodically inspected and adjusted, as necessary, as part of the structure's maintenance program. Where paving or flatwork abuts the structure, a maintenance program should be established to effectively seal and maintain joints and prevent surface water infiltration.

Temple at the Nielson Site | Cody, Wyoming March 28, 2023 | Terracon Project No. 26235004



Earthwork Construction Considerations

Shallow excavations for the proposed structure are anticipated to be accomplished with conventional construction equipment. Upon completion of filling and grading, care should be taken to maintain the subgrade water content prior to construction of gradesupported improvements such as floor slabs and pavements. Construction traffic over the completed subgrades should be avoided. The site should also be graded to prevent ponding of surface water on the prepared subgrades or in excavations. Water collecting over or adjacent to construction areas should be removed. If the subgrade freezes, desiccates, saturates, or is disturbed, the affected material should be removed, or the materials should be scarified, moisture conditioned, and recompacted prior to floor slab construction.

As a minimum, excavations should be performed in accordance with OSHA 29 CFR, Part 1926, Subpart P, "Excavations" and its appendices, and in accordance with any applicable local and/or state regulations.

Construction site safety is the sole responsibility of the contractor who controls the means, methods, and sequencing of construction operations. Under no circumstances shall the information provided herein be interpreted to mean Terracon is assuming responsibility for construction site safety or the contractor's activities; such responsibility shall neither be implied nor inferred.

Excavations or other activities resulting in ground disturbance have the potential to affect adjoining properties and structures. Our scope of services does not include review of available final grading information or consider potential temporary grading performed by the contractor for potential effects such as ground movement beyond the project limits. A preconstruction/ precondition survey should be conducted to document nearby property/infrastructure prior to any site development activity. Excavation or ground disturbance activities adjacent or near property lines should be monitored or instrumented for potential ground movements that could negatively affect adjoining property and/or structures.

Construction Observation and Testing

The earthwork efforts should be observed by the Geotechnical Engineer (or others under their direction). Observation should include documentation of adequate removal of surficial materials (vegetation, topsoil, and rootmats), evaluation and remediation of existing fill materials, as well as proofrolling and mitigation of unsuitable areas delineated by the proofroll.

Each lift of compacted fill should be tested, evaluated, and reworked, as necessary, as recommended by the Geotechnical Engineer prior to placement of additional lifts. Each lift of fill should be tested for density and water content at a frequency of at least one

Temple at the Nielson Site | Cody, Wyoming March 28, 2023 | Terracon Project No. 26235004



test for every 2,500 square feet of compacted fill in the building areas and 5,000 square feet in pavement areas. Where not specified by local ordinance, one density and water content test should be performed for every 100 linear feet of compacted utility trench backfill and a minimum of one test performed for every 12 vertical inches of compacted backfill.

In areas of foundation excavations, the bearing subgrade should be evaluated by the Geotechnical Engineer. If unanticipated conditions are observed, the Geotechnical Engineer should prescribe mitigation options.

In addition to the documentation of the essential parameters necessary for construction, the continuation of the Geotechnical Engineer into the construction phase of the project provides the continuity to maintain the Geotechnical Engineer's evaluation of subsurface conditions, including assessing variations and associated design changes.

Shallow Foundations

The primary geotechnical consideration for the Temple site is to provide uniform bearing within the native gravel while limiting potential for differential settlement. To accomplish this, proper preparation of the native gravel subgrade in accordance with the requirements noted in **Earthwork** is critical to limiting differential movement, as the gravel soils provide substantial bearing capacity for the type of building construction planned. The following design parameters are applicable for shallow foundations if the requirements of the **Earthwork** section are adhered to.

Design Parameters - Compressive Loads

Item	Description	
Maximum Net Allowable Bearing Pressure 1, 2	3,500 psf	
Required Bearing Stratum ³	Properly prepared native gravel, or Structural Fill replacement fill	
Minimum Foundation Dimensions	Per IBC 1809.7	
Ultimate Passive Resistance ⁴ (equivalent fluid pressures)	190 pcf (cohesive backfill) 460 pcf (granular backfill)	
Ultimate Coefficient of Sliding Resistance ⁵	0.60 coefficient of friction - granular materia	
Minimum Embedment below Finished Grade ⁶	Exterior footings in unheated areas: 48 inches Interior footings in heated areas: 18 inches	

Temple at the Nielson Site | Cody, Wyoming March 28, 2023 | Terracon Project No. 26235004



Item	Description
Estimated Total Settlement from Structural Loads ²	Less than about ¾ inch
Estimated Differential Settlement 2, 7	About $\frac{1}{2}$ to $\frac{2}{3}$ of total settlement

- 1. The maximum net allowable bearing pressure is the pressure in excess of the minimum surrounding overburden pressure at the footing base elevation. Values assume that exterior grades are no steeper than 20% within 10 feet of structure. Based on a minimum factor of safety of 3.
- 2. Values provided are for maximum loads noted in **Project Description**. Additional geotechnical consultation will be necessary if higher loads are anticipated.
- 3. Unsuitable or soft soils should be overexcavated and replaced per the recommendations presented in **Earthwork**.
- 4. Use of passive earth pressures require the sides of the excavation for the spread footing foundation to be nearly vertical and the concrete placed neat against these vertical faces or that the footing forms be removed and compacted Structural Fill be placed against the vertical footing face. Assumes no hydrostatic pressure. A minimum factor of safety of 2 should be applied to ultimate values.
- 5. Can be used to compute sliding resistance where foundations are placed on suitable soil/materials. Frictional resistance for granular materials is dependent on the bearing pressure which may vary due to load combinations. For fine-grained materials, lateral resistance using cohesion should not exceed ½ the dead load, also application of a minimum factor of safety of 2 should be utilized.
- 6. Embedment necessary to minimize the effects of frost and/or seasonal water content variations. For sloping ground, maintain depth below the lowest adjacent exterior grade within 5 horizontal feet of the structure.
- 7. Differential settlements are noted for equivalent-loaded foundations and bearing elevation as measured over a span of 50 feet.


Foundation Construction Considerations

As noted in **Earthwork**, the footing excavations should be evaluated under the observation of the Geotechnical Engineer. The base of all foundation excavations should be free of water and loose soil, prior to placing concrete. Concrete should be placed soon after excavating to reduce bearing soil disturbance. Care should be taken to prevent wetting or drying of the bearing materials during construction. Excessively wet or dry material or any loose/disturbed material in the bottom of the footing excavations should be removed/reconditioned before foundation concrete is placed.


If unsuitable bearing soils are observed at the base of the planned footing excavation, the excavation should be extended deeper to suitable soils, and the footings could bear directly on these soils at the lower level or on lean concrete backfill placed in the excavations. The lean concrete replacement zone is illustrated on the sketch below.

Temple at the Nielson Site | Cody, Wyoming March 28, 2023 | Terracon Project No. 26235004





Overexcavation for Structural Fill placement below footings should be conducted as shown below. The overexcavation should be backfilled up to the footing base elevation, with Structural Fill placed and compacted as recommended in the **Earthwork** section.



Floor Slabs

Design parameters for floor slabs assume the requirements for **Earthwork** have been followed. Specific attention should be given to positive drainage away from the structure and positive drainage of the aggregate base beneath the floor slab.

Floor Slab Design Parameters

Item	Description
Floor Slab Support ^{1,2}	Properly prepared native gravel or Structural Fill replacement material below a minimum of 6 inches of crushed base course Subgrade compacted to recommendations in Earthwork

Temple at the Nielson Site | Cody, Wyoming March 28, 2023 | Terracon Project No. 26235004



Item	Description
Estimated Modulus	
of Subgrade	250 pounds per square inch per inch (psi/in) for point loads
Reaction ³	

- 1. Crushed aggregate base course in accordance with Wyoming Public Work Standard Specifications, Section 02190, Grading W.
- 2. Floor slabs should be structurally independent of building footings or walls to reduce the possibility of floor slab cracking caused by differential movements between the slab and foundation.
- 3. Modulus of subgrade reaction is an estimated value based upon our experience with the subgrade condition, the requirements noted in **Earthwork**, and the floor slab support as noted in this table. It is provided for point loads. For large area loads the modulus of subgrade reaction would be lower.

The use of a vapor retarder should be considered beneath concrete slabs on grade covered with wood, tile, carpet, or other moisture sensitive or impervious coverings, when the project includes humidity-controlled areas, or when the slab will support equipment sensitive to moisture. When conditions warrant the use of a vapor retarder, the slab designer should refer to ACI 302 and/or ACI 360 for procedures and cautions regarding the use and placement of a vapor retarder.

Saw-cut contraction joints should be placed in the slab to help control the location and extent of cracking. For additional recommendations, refer to the ACI Design Manual. Joints or cracks should be sealed with a waterproof, non-extruding compressible compound specifically recommended for heavy duty concrete pavement and wet environments.

Where floor slabs are tied to perimeter walls or turn-down slabs to meet structural or other construction objectives, our experience indicates differential movement between the walls and slabs will likely be observed in adjacent slab expansion joints or floor slab cracks beyond the length of the structural dowels. The Structural Engineer should account for potential differential settlement through use of sufficient control joints, appropriate reinforcing or other means.

Floor Slab Construction Considerations

Finished subgrade, within and for at least 10 feet beyond the floor slab, should be protected from traffic, rutting, or other disturbance and maintained in a relatively moist condition until floor slabs are constructed. If the subgrade should become damaged or desiccated prior to construction of floor slabs, the affected material should be removed, and Structural Fill should be added to replace the resulting excavation. Final conditioning

Temple at the Nielson Site | Cody, Wyoming March 28, 2023 | Terracon Project No. 26235004



of the finished subgrade should be performed immediately prior to placement of the floor slab support course.

The Geotechnical Engineer should observe the condition of the floor slab subgrades immediately prior to placement of the floor slab support course, reinforcing steel, and concrete. Attention should be paid to high traffic areas that were rutted and disturbed earlier, and to areas where backfilled trenches are located.

Below-Grade Structures

It is our understanding that a basement level, approximately 15 to 20 feet below finished grade, will be included below the main portion of the temple. This basement level will likely include placement of slab-on-grade floor and will be deep enough that it is likely to act as a compensated foundation. That is, the added stress from the structure (foundation and/or slab) will be less than the overburden pressure from the soil removed. Therefore, settlement of the foundations will be largely dependent upon earthwork quality and removal of loose material. Recompacting of subgrade will be important to overall performance. Inclusion of water stop between exterior footings and exterior foundation walls should be included in the design to reduce the potential for surface infiltrated moisture to enter the below grade spaces at the construction joint.

Lateral Earth Pressures


We understand that a retaining wall is planned along the north portion of the site to allow for pavement of the area near the past slope instability/slump feature. Based on our slope stability analysis, the gravel slope in the vicinity of the failure is stable in a global stability model. The use of the retaining wall will be required to provide a nominal 4 to 5 feet of fill for site grading to allow for use of the area for pavements and landscaping. Based on the global stability, the design of a retaining wall should include the following lateral earth parameters as well as embedment to a depth of no less than 7.5 feet below existing grade to provide bearing support within the lower dense to very dense gravel layer to keep global stability factors of safety above 1.5. Bearing capacity at this depth will be at least 3,500 psf for foundation bearing of the wall system. This will allow for substantial embedment on the downslope side of the retaining wall, and the internal stability of the design will need to be evaluated by Haskell. Terracon will need to review the final design to check for consistency of design with the parameters provided, as required by our contract.

Temple at the Nielson Site | Cody, Wyoming March 28, 2023 | Terracon Project No. 26235004



Design Parameters

Structures with unbalanced backfill levels on opposite sides should be designed for earth pressures at least equal to values indicated in the following table. Earth pressures will be influenced by structural design of the walls, conditions of wall restraint, methods of construction, and/or compaction and the strength of the materials being restrained. Two wall restraint conditions are shown in the diagram below. Active earth pressure is commonly used for design of free-standing cantilever retaining walls and assumes wall movement. The "at-rest" condition assumes no wall movement and is commonly used for basement walls, loading dock walls, or other walls restrained at the top. The recommended design lateral earth pressures do not include a factor of safety and do not provide for possible hydrostatic pressure on the walls (unless stated).



Lateral Earth Pressure Design Parameters

Earth Pressure Condition ¹	Coefficient for Backfill Type ²	Surcharge Pressure ³ p ₁ (psf)	Equivalent Fluid Pressures (psf) ^{2,4,5}
Active (Ka)	Native Upper Gravel - 0.33	(0.33)S	(40)H
Active (Ra)	Imported Structural Fill - 0.27	(0.27)S	(35)H
At-Post (Ko)	Native Upper Gravel - 0.50	(0.50)S	(65)H
At-Rest (Ko)	Imported Structural Fill - 0.43	(0.43)S	(55)H

- 1. For active earth pressure, wall must rotate about base, with top lateral movements 0.002 H to 0.004 H, where H is wall height. For passive earth pressure, wall must move horizontally to mobilize resistance. Fat clay or other expansive soils should not be used as backfill behind the wall.
- 2. Uniform, horizontal backfill, with a maximum unit weight of 125 pcf for native upper gravel soils and 130 pcf for Structural Fill (imported).
- 3. Uniform surcharge, where S is surcharge pressure.
- 4. Loading from heavy compaction equipment is not included.
- 5. To achieve "Unsaturated" conditions, follow guidelines in **Subsurface Drainage** for **Below-Grade Walls** below.

Temple at the Nielson Site | Cody, Wyoming March 28, 2023 | Terracon Project No. 26235004




Backfill placed against structures should consist of granular soils or low plasticity cohesive soils. For the granular values to be valid, the granular backfill must extend out and up from the base of the wall at an angle of at least 45 degrees from vertical for the active case.

Footings, floor slabs or other loads bearing on backfill behind walls may have a significant influence on the lateral earth pressure. Placing footings within wall backfill and in the zone of active soil influence on the wall should be avoided unless structural analyses indicate the wall can safely withstand the increased pressure.

The lateral earth pressure recommendations given in this section are applicable to the design of rigid retaining walls subject to slight rotation, such as cantilever, or gravity type concrete walls. These recommendations are not applicable to the design of modular block - geogrid reinforced backfill walls (also termed MSE walls). Recommendations covering these types of wall systems are beyond the scope of services for this assignment. However, we would be pleased to develop a proposal for evaluation and design of such wall systems upon request.

Subsurface Drainage for Below-Grade Walls

A perforated rigid plastic drain line installed behind the base of walls and extends below adjacent grade is recommended to prevent hydrostatic loading on the walls. The invert of a drain line around a below-grade building area or exterior retaining wall should be placed near foundation bearing level. The drain line should be sloped to provide positive gravity drainage to daylight or to a sump pit and pump. The drain line should be surrounded by clean, free-draining granular material having less than 5% passing the No. 200 sieve, such as No. 57 aggregate. The free-draining aggregate should be encapsulated in a filter fabric. The granular fill should extend to within 2 feet of final grade, where it should be capped with compacted cohesive fill to reduce infiltration of surface water into the drain system.



Temple at the Nielson Site | Cody, Wyoming March 28, 2023 | Terracon Project No. 26235004



As an alternative to free-draining granular fill, a prefabricated drainage structure may be used. A prefabricated drainage structure is a plastic drainage core or mesh which is covered with filter fabric to prevent soil intrusion and is fastened to the wall prior to placing backfill.

Pavements

General Pavement Comments

The pavement section recommendations provided are based on the subsurface profile and laboratory testing of bulk samples obtained from the subgrade encountered during our field exploration. Pavement designs are provided for the traffic conditions and pavement life conditions as noted in **Project Description** and in the following sections of this report. A critical aspect of pavement performance is site preparation. Pavement designs noted in this section must be applied to the site which has been prepared as recommended in the **Earthwork** section. The pavement section recommendations provided below are suitable for traffic support as discussed within each section upon the fully constructed pavement section. These sections, or portions of the constructed section, have not been designed to support channelized and high-intensity traffic loading associated with construction traffic such as concrete trucks for placements, aggregate or asphalt haul trucks.

Pavement Design Parameters

Designs for minimum thicknesses for new pavement sections for this project have been based on the procedures outlined in the 1993 Guideline for Design of Pavement Structures by the American Association of State Highway and Transportation Officials (AASHTO-1993). Pavement design methods are intended to provide structural sections with adequate thickness over a particular subgrade such that wheel loads are reduced to a level the subgrade can support. The support characteristics of the subgrade for pavement design do not account for shrink/swell movements of subgrade soils. Thus, the pavement may be adequate from a structural standpoint, yet still experience cracking and deformation due to shrink/swell related movement of the subgrade.

To analyze pavement subgrade support, a composite bulk sample was obtained throughout the anticipated pavement areas. The controlling subgrade material (alluvial deposits, generally classified as clayey sand with gravel) was collected and laboratory-soaked CBR performed at a single point condition during our previous exploration conducted at this site. The single point soaked California Bearing Ratio (CBR) condition resulted in a value of 8.0 for the controlling subgrade which was utilized in the analysis discussed below.

Temple at the Nielson Site | Cody, Wyoming March 28, 2023 | Terracon Project No. 26235004



Our analysis has been conducted assuming the minimum required traffic based on The Church's requirements for new construction of parking lots. We expect that primary traffic will consist of passenger vehicles with substantial personal auto/light trucks along with limited daily light delivery vehicles (FedEx, UPS, similar) and with weekly trash collection. We have assumed that the combined traffic can be considered in two scenarios, Light Duty for parking and areas of limited traffic and Medium Duty for areas of more substantial drive lane traffic. For these cases we have assumed a total load coverage equivalent of approximately six weekly 18-kip single axle loads (ESALs) for Light Duty and 15 weekly ESALs for Medium Duty. Based on these assumptions, an estimated 30,000 ESALs represent the design traffic intensity for Light Duty pavements and an estimated 60,000 ESALs represent the design traffic intensity for Medium Duty pavements over an approximate 40-year design period. For analysis an initial serviceability index of 4.2, a terminal serviceability index of 2.0, standard deviation of 0.45, and reliability of 90 percent have been utilized for section thickness development.

A modulus of subgrade reaction of about 150 pci was used for the PCC pavement designs. The values were based upon the controlling CBR value of 8.0 and correlated to k-value for rigid pavement design based on published data and our experience with the clayey sand subgrade soils and our understanding of the quality of the subgrade as prescribed by the **Site Preparation** conditions as outlined in **Earthwork**. A modulus of rupture of 580 psi was used for pavement concrete.

Pavement Subgrade Preparation

For all areas to receive new asphalt pavement sections, we recommend that the upper 12 inches of the subgrade be scarified, moisture conditioned and compacted to 95 percent of the maximum laboratory dry density value in accordance with ASTM D698 prior to placement of pavement section components. The subgrade should be evaluated and tested for compliance with these conditions within 24 hours of commencement of pavement operations to ensure that the moisture content and density values are within recommended ranges. Areas not in compliance should be moisture conditioned and recompacted. Areas where unsuitable conditions (as delineated by proof-rolling subsequent compaction testing) are located should be repaired either by reworking the existing soil or removing and replacing the soil with properly compacted fills. If a significant precipitation event occurs after the evaluation or if the surface becomes disturbed, the subgrade should be reviewed by a qualified individual immediately prior to placement of base course. The subgrade should be in its finished form at the time of the final review.

Pavement Section Thicknesses

The following table provides our opinion of minimum thickness for AC sections:

Temple at the Nielson Site | Cody, Wyoming March 28, 2023 | Terracon Project No. 26235004



Asphaltic Concrete Design

Layer	Thickness (inches		
Layer	Light Duty ¹	Medium Duty ²	Specifications
Subgrade	Upper 12 inches of existing soil	Upper 12 inches of existing soil	95% of maximum dry density per ASTM D698, +/-3% of Optimum Moisture Content (OMC)
Crushed Base Course	8	9	WPWSS, Section 02190, Grading W
Asphalt Concrete	3	4	WPWSS, Section 02510
Total Pavement Section	11	13	

- 1. Light Duty Pavement was designed for a total of 30,000 ESALs.
- 2. Heavy Duty Pavement was designed for a total of 60,000 ESALs.

We recommend that Portland cement concrete (PCC) pavement be utilized in entrance and exit sections, dumpster pads, and other areas where extensive wheel maneuvering is expected. Heavy duty pavement design for the apron was based on 60,000 ESALs. The following table provides our estimated minimum thickness of PCC pavements.

Portland Cement Concrete Design

Layer	TI	hickness (inches)	
Layei	Thickness (inches)	Specifications	
Subgrade	Upper 12 inches of existing soil	95% of maximum dry density per ASTM D698, +/-3% of Optimum Moisture Content (OMC)	
Crushed Base Course	4	WPWSS, Section 02190, Grading W	
PCC (reinforced)	6	WPWSS, Section 02520	
Total Pavement Section	10		

Temple at the Nielson Site | Cody, Wyoming March 28, 2023 | Terracon Project No. 26235004



Although not required for structural support, a minimum 4-inch thick base course layer is recommended to help reduce potential for slab curl, shrinkage cracking, and subgrade pumping through joints. Proper joint spacing will also be required to prevent excessive slab curling and shrinkage cracking. Joints should be sealed to prevent entry of foreign material and doweled where necessary for load transfer. PCC pavement details for joint spacing, joint reinforcement, and joint sealing should be prepared in accordance with ACI 330 and ACI 325.

Where practical, we recommend early-entry cutting of crack-control joints in PCC pavements. Cutting of the concrete in its "green" state typically reduces the potential for micro-cracking of the pavements prior to the crack control joints being formed, compared to cutting the joints after the concrete has fully set. Micro-cracking of pavements may lead to crack formation in locations other than the sawed joints, and/or reduction of fatigue life of the pavement.

Openings in pavements, such as decorative landscaped areas, are sources for water infiltration into surrounding pavement systems. Water can collect in the islands and migrate into the surrounding subgrade soils thereby degrading support of the pavement. Islands with raised concrete curbs, irrigated foliage, and low permeability near-surface soils are particular areas of concern. The civil design for the pavements with these conditions should include features to restrict or collect and discharge excess water from the islands. Examples of features are edge drains connected to the stormwater collection system, longitudinal subdrains, or other suitable outlets and impermeable barriers preventing lateral migration of water such as a cutoff wall installed to a depth below the pavement structure.

The Portland cement concrete mix design should be designed with proper airentrainment and have a minimum compressive strength of 4,000 psi after 28 days of laboratory curing. Adequate reinforcement and number of longitudinal and transverse control joints should be placed in the rigid pavement in accordance with ACI requirements. The joints should be sealed as soon as possible (in accordance with the sealant manufacturer's instructions) to minimize infiltration of water into the soil.

Pavement Drainage

Pavements should be sloped to provide rapid drainage of surface water. Water allowed to pond on or adjacent to the pavements could saturate the subgrade and contribute to premature pavement deterioration. In addition, the pavement subgrade should be graded to provide positive drainage within the granular base section. Appropriate subdrainage or connection to a suitable daylight outlet should be provided to remove water from the granular subbase.

Temple at the Nielson Site | Cody, Wyoming March 28, 2023 | Terracon Project No. 26235004



Pavement Maintenance

The pavement sections represent minimum recommended thicknesses and, as such, periodic upkeep should be anticipated. Preventive maintenance should be planned and provided for through an on-going pavement management program. Maintenance activities are intended to slow the rate of pavement deterioration and to preserve the pavement investment. Pavement care consists of both localized (e.g., crack and joint sealing and patching) and global maintenance (e.g., surface sealing). Additional engineering consultation is recommended to determine the type and extent of a cost-effective program. Even with periodic maintenance, some movements and related cracking may still occur, and repairs may be required.

Pavement performance is affected by its surroundings. In addition to providing preventive maintenance, the civil engineer should consider the following recommendations in the design and layout of pavements:

- Final grade adjacent to paved areas should slope down from the edges at a minimum 2%.
- Subgrade and pavement surfaces should have a minimum 2% slope to promote proper surface drainage.
- Install pavement drainage systems surrounding areas anticipated for frequent wetting.
- Install joint sealant and seal cracks immediately.
- Seal all landscaped areas in or adjacent to pavements to reduce moisture migration to subgrade soils.
- Place compacted, low permeability backfill against the exterior side of curb and gutter.
- Place curb, gutter and/or sidewalk directly on clay subgrade soils rather than on unbound granular base course materials.

Frost Considerations

The gravel soils located on the site have limited frost susceptibility; however, the clay soils located near the east side (from the previous site exploration) of the site to depths between 1.5 and 2.0 feet below existing grade and the clay soils located along the south access road to depths between 4.0 and 7.5 feet below existing grade are frost susceptible. Where clay subgrades are encountered small amounts of water can affect the performance of the slabs on-grade, sidewalks, and pavements. Exterior slabs should be anticipated to heave during winter months. If frost action needs to be eliminated in critical areas, we recommend the use of non-frost susceptible (NFS) fill or structural slabs (for instance, structural stoops in front of building doors). Placement of NFS

Temple at the Nielson Site | Cody, Wyoming March 28, 2023 | Terracon Project No. 26235004



material in large areas may not be feasible; however, the following recommendations are provided to help reduce potential frost heave:

- Provide surface drainage away from the building and slabs, and toward the site drainage system.
- Install drains around the perimeter of the building, stoops, below exterior slabs and pavements, and connect them to the site drainage system.
- Grade clayey subgrades so groundwater potentially perched in overlying fill or aggregate base, slope toward a site drainage system.
- Place NFS fill as backfill beneath slabs and pavements critical to the project.
- Place a 3 horizontal to 1 vertical (3H:1V) transition zone between NFS fill and other soils.
- Place NFS materials in critical sidewalk areas.

As an alternative to extending NFS fill to the full frost depth, consideration can be made to placing extruded polystyrene or cellular concrete under a buffer of at least 2 feet of NFS material.

General Comments

Our analysis and opinions are based upon our understanding of the project, the geotechnical conditions in the area, and the data obtained from our site exploration. Variations will occur between exploration point locations or due to the modifying effects of construction or weather. The nature and extent of such variations may not become evident until during or after construction. Terracon should be retained as the Geotechnical Engineer, where noted in this report, to provide observation and testing services during pertinent construction phases. If variations appear, we can provide further evaluation and supplemental recommendations. If variations are noted in the absence of our observation and testing services on-site, we should be immediately notified so that we can provide evaluation and supplemental recommendations.

Our Scope of Services does not include either specifically or by implication any environmental or biological (e.g., mold, fungi, bacteria) assessment of the site or identification or prevention of pollutants, hazardous materials or conditions. If the owner is concerned about the potential for such contamination or pollution, other studies should be undertaken.

Our services and any correspondence are intended for the sole benefit and exclusive use of our client for specific application to the project discussed and are accomplished in accordance with generally accepted geotechnical engineering practices with no third-party beneficiaries intended. Any third-party access to services or correspondence is solely for information purposes to support the services provided by Terracon to our

Temple at the Nielson Site | Cody, Wyoming March 28, 2023 | Terracon Project No. 26235004



client. Reliance upon the services and any work product is limited to our client and is not intended for third parties. Any use or reliance of the provided information by third parties is done solely at their own risk. No warranties, either express or implied, are intended or made.

Site characteristics as provided are for design purposes and not to estimate excavation cost. Any use of our report in that regard is done at the sole risk of the excavating cost estimator as there may be variations on the site that are not apparent in the data that could significantly effect excavation cost. Any parties charged with estimating excavation costs should seek their own site characterization for specific purposes to obtain the specific level of detail necessary for costing. Site safety and cost estimating including excavation support and dewatering requirements/design are the responsibility of others. Construction and site development have the potential to affect adjacent properties. Such impacts can include damages due to vibration, modification of groundwater/surface water flow during construction, foundation movement due to undermining or subsidence from excavation, as well as noise or air quality concerns. Evaluation of these items on nearby properties are commonly associated with contractor means and methods and are not addressed in this report. The owner and contractor should consider a preconstruction/precondition survey of surrounding development. If changes in the nature, design, or location of the project are planned, our conclusions and recommendations shall not be considered valid unless we review the changes and either verify or modify our conclusions in writing.

Temple at the Nielson Site | Cody, Wyoming March 28, 2023 | Terracon Project No. 26235004




Figures

Contents:

GeoModel (3 pages; Building Area, Pavement Area, Retaining Wall)



GeoModel - Building Area




This is not a cross section. This is intended to display the Geotechnical Model only. See individual logs for more detailed conditions.


Model Layer	Layer Name	General Description
1	Upper Gravel	Well-Graded GRAVEL with Silt and Sand OR Silty Gravel with Sand, fine grained, subangular, light brown, dry, medium dense
2	Lower Gravel	Poorly-Graded GRAVEL with Silt and Sand, coarse grained, subrounded, light brown to gray, dry, medium dense to very dense, some cobbles
3	Clay	Sandy Fat CLAY, medium to high plasticity, brown, moist, stiff to very stiff
4	Bedrock	CLAYSTONE, tan, moist, fine-grained, moderately fractured, thin bedding, highly weathered, weak rock, interbedded sandstone layer


LEGEND











NOTES:

Layering shown on this figure has been developed by the geotechnical engineer for purposes of modeling the subsurface conditions as required for the subsequent geotechnical engineering for this project. Numbers adjacent to soil column indicate depth below ground surface.



GeoModel - Pavement Area




This is not a cross section. This is intended to display the Geotechnical Model only. See individual logs for more detailed conditions.

Model Layer	Layer Name	General Description
1	Upper Gravel	Well-Graded GRAVEL with Silt and Sand OR Silty Gravel with Sand, fine grained, subangular, light brown, dry, medium dense
2	Lower Gravel	Poorly-Graded GRAVEL with Silt and Sand, coarse grained, subrounded, light brown to gray, dry, medium dense to very dense, some cobbles
3	Clay	Sandy Fat CLAY, medium to high plasticity, brown, moist, stiff to very stiff
4	Bedrock	CLAYSTONE, tan, moist, fine-grained, moderately fractured, thin bedding, highly weathered, weak rock, interbedded sandstone layer

LEGEND






NOTES:

Layering shown on this figure has been developed by the geotechnical engineer for purposes of modeling the subsurface conditions as required for the subsequent geotechnical engineering for this project. Numbers adjacent to soil column indicate depth below ground surface.



GeoModel - Retaining Wall





This is not a cross section. This is intended to display the Geotechnical Model only. See individual logs for more detailed conditions.

Model Layer	Layer Name	General Description
1	Upper Gravel	Well-Graded GRAVEL with Silt and Sand OR Silty Gravel with Sand, fine grained, subangular, light brown, dry, medium dense
2	Lower Gravel	Poorly-Graded GRAVEL with Silt and Sand, coarse grained, subrounded, light brown to gray, dry, medium dense to very dense, some cobbles
3	Clay	Sandy Fat CLAY, medium to high plasticity, brown, moist, stiff to very stiff
4	Bedrock	CLAYSTONE, tan, moist, fine-grained, moderately fractured, thin bedding, highly weathered, weak rock, interbedded sandstone layer

LEGEND







NOTES:

Layering shown on this figure has been developed by the geotechnical engineer for purposes of modeling the subsurface conditions as required for the subsequent geotechnical engineering for this project. Numbers adjacent to soil column indicate depth below ground surface.

Temple at the Nielson Site | Cody, Wyoming March 28, 2023 | Terracon Project No. 26235004



Attachments

Temple at the Nielson Site | Cody, Wyoming March 28, 2023 | Terracon Project No. 26235004



Exploration and Testing Procedures

Field Exploration

Number of Borings	Approximate Boring Depth (feet)	Location
5	18.0 to 41.5	Building Area
5	10.4 to 11.5	Pavement Areas
4	21.5	Retaining Wall Alignment

Boring Layout and Elevations: Terracon personnel provided the boring layout using handheld GPS equipment (estimated horizontal accuracy of about ± 10 feet) and referencing existing site features. Approximate ground surface elevations were estimated using Google Earth. If elevations and a more precise boring layout are desired, we recommend borings be surveyed.

Subsurface Exploration Procedures: We advanced the borings between February 14 and February 17, 2023, using a subcontracted truck-mounted, rotary drill rig operated by Haztech Drilling of Billings, Montana using continuous flight augers (hollow stem). In general, four samples were obtained in the upper 10 feet of each boring and at intervals of 5 feet thereafter. Bulk samples were collected in the upper 5 feet of the borings, as needed. In the thin-walled tube sampling procedure, a thin-walled, seamless steel tube with a sharp cutting edge was pushed hydraulically into the soil to obtain a relatively undisturbed sample. In the split-barrel sampling procedure, a standard 2-inch outer diameter split-barrel sampling spoon was driven into the ground by a 140-pound automatic hammer falling a distance of 30 inches. The number of blows required to advance the sampling spoon the last 12 inches of a normal 18-inch penetration is recorded as the Standard Penetration Test (SPT) resistance value. The SPT resistance values, also referred to as N-values, are indicated on the boring logs at the test depths. We observed and recorded groundwater levels during drilling and sampling. For safety purposes, all borings were backfilled with auger cuttings after their completion.

The sampling depths, penetration distances, and other sampling information was recorded on the field boring logs. The samples were placed in appropriate containers and taken to our soil laboratory for testing and classification by a Geotechnical Engineer. Our exploration team prepared field boring logs as part of the drilling operations. These field logs included visual classifications of the materials observed during drilling and our interpretation of the subsurface conditions between samples. Final boring logs were prepared from the field logs. The final boring logs represent the Geotechnical Engineer's interpretation of the field logs and include modifications based on observations and tests of the samples in our laboratory.

Temple at the Nielson Site | Cody, Wyoming March 28, 2023 | Terracon Project No. 26235004



Other Testing: In addition to the borings outlined in the table above, we performed percolation tests, indicated by the designation I-1 through I-5 on the Exploration Plan, in general accordance with the City of Cody Public Works requirements at five locations on the site. The results of the percolation tests are summarized and provided with the exploration results below.

Laboratory Testing

The project engineer reviewed the field data and assigned laboratory tests. The laboratory testing program included the following types of tests:

- Moisture Content
- Dry Unit Weight
- Consolidation/Swell
- Unconfined Compression
- Atterberg Limits

The laboratory testing program often included examination of soil samples by an engineer. Based on the results of our field and laboratory programs, we described and classified the soil samples in accordance with the Unified Soil Classification System.

Rock classification was conducted using locally accepted practices for engineering purposes; petrographic analysis may reveal other rock types. Rock core samples typically provide an improved specimen for this classification. Boring log rock classification was determined using the Description of Rock Properties.

Other Testing: Soil analytical testing for water soluble sulfate, resistivity, and pH were performed by Energy Laboratories in Billings, Montana. Results are attached.

Temple at the Nielson Site | Cody, Wyoming March 28, 2023 | Terracon Project No. 26235004



Photography Log



View looking East from Boring B-9



View looking North from Boring B-9

Temple at the Nielson Site | Cody, Wyoming March 28, 2023 | Terracon Project No. 26235004





View looking South from Boring B-9



View looking West from Boring B-9

Temple at the Nielson Site | Cody, Wyoming March 28, 2023 | Terracon Project No. 26235004



Site Location and Exploration Plans

Contents:

Site Location Plan Exploration Plan

Note: All attachments are one page unless noted above.

Temple at the Nielson Site | Cody, Wyoming March 28, 2023 | Terracon Project No. 26235004




Site Location



Temple at the Nielson Site | Cody, Wyoming March 28, 2023 | Terracon Project No. 26235004



Exploration Plan



Exploration and Laboratory Results

Contents:

Boring Logs (B-8 through B-12, P-6 through P-10, and RW-1 through RW-4) $\,$

Atterberg Limits Grain Size Distribution (2 pages) Consolidation/Swell Unconfined Compressive Strength Corrosivity (7 pages)

Note: All attachments are one page unless noted above.



					_								
er) gc	Location: See Exploration Plan	_	<u>~</u> &	oe Oe	L	St	rength 1	Гest	(%)	E	Atterberg Limits	
Model Layer	Graphic Log	Latitude: 44.5118° Longitude: -109.0822°	Depth (Ft.)	Water Level Observations	Sample Type	Field Test Results	ē	e c	(%)	Water Content (%)	Dry Unit Weight (pcf)		1
le	phi	Latitude: 44.5110 Longitude: -105.0022	급	erL	ble	gld -	Test Type	essir igth f)	Strain (%)	Vat	ry L ght		
10d	<u>r</u> a		Эер	Nat Obse	San	F ~	. ts	ren (ps	ain	\ Juo	Veig	LL-PL-PI	
_		Depth (Ft.)		70	0,		¹	Compressive Strength (psf)	Str		>		
	091	WELL GRADED GRAVEL WITH SILT AND SAND			7								
	$\bigcirc \bigcirc \bigcirc$	(GW-GM), fine grained, subangular, brown, moist,			IX	6-6-7				15.6			
	100 D	medium dense to dense, homogeneous	-		//	N=13							
	6 X Z												
	646		_										
			_		\mathbb{N}	11 16 14							
1					ΙX	11-16-14 N=30				2.7			
•	54		_										
	00												
	000		5 –	-									-
	60 D				$ \vee $	11-9-10				3.1		NP	
	ρĂŒ		-	1	$ \Lambda $	N=19				3.1		INF	
	6 Q K	7.0											1
	6 9	POORLY GRADED GRAVEL WITH SILT AND SAND	-	1									
		(GP-GM), with cobbles, coarse grained, subrounded,			7		1						
	0	brown, dry, very dense, homogeneous	-	1	X	16-25-25 N=50				3.7			
					$/ \setminus$	UC=NI							
			-										
			10-	1									
	0 0		10		$\mathbb{N}/$								
	00		_		ΙX	33-42-50/5"				3.5			
	00												
	000		_	-									
	0												
	b Q C		-	1									
			_										
			4.5										
			15-		\times	50/5"				4.0			
2	O		_										
	000												
	0		_										
	b O												
			_	1									
	. 0		-	1									
	00		20-		><	50/1"							
	0 ()												
	0		-	1									
	6 Z C		_										
	6 🛁												
			_	1									
			-	-									
	00												
	a A d		25										
See	Explor	ation and Testing Procedures for a description of field and laboratory		W	/ater	Level Observation	าร					Drill Rig	
prod	cedures	s used and additional data (If any).				None						BK-81	
See	Suppo	rting Information for explanation of symbols and abbreviations.				Observed						Hammer Typ	e
												Automatic	
												Driller Haztech / P. B	rav
Not					dvan SA	cement Method							пау
Elev	ation F	Reference: Elevations were obtained from Google Earth		11.	<i>3</i> A							Logged by TJ Trussell	
													a d
				А	band	onment Method						Boring Starte 02-14-2023	ea
						backfilled with auge	er cutt	ings upo	n comp	oletion.		Boring Comp	leted
												02-14-2023	



_													
er) gc	Location: See Exploration Plan		<u>~</u> &	ec .	L	St	rength 1	Γest	(%)	. (5	Atterberg Limits	
Model Layer	Graphic Log	Latitude: 44.5118° Longitude: -109.0822°	Depth (Ft.)	Water Level Observations	Sample Type	Field Test Results	ā	Compressive Strength (psf)	(0)	Water Content (%)	Dry Unit Weight (pcf)		
<u>e</u>	phi	Latitude: 44.5116 Longitude: -105.0022	급	erL	aldı	gld -	Test Type	essir igth f)	Strain (%)	Vat	ry L ght		
Jod	Gra)ep	Nat Obse	San	Fie R	. sst	ren (ps	rain	700	Veig	LL-PL-PI	
_		Depth (Ft.)	"	-0	0)		<u> </u>	St	Stı		>		
	مير ر	POORLY GRADED GRAVEL WITH SILT AND SAND			/								
		(GP-GM), with cobbles, coarse grained, subrounded,			IXI	14-27-41 N=68				8.6			
		brown, dry, very dense, homogeneous (continued)			$/\setminus$	11-00							
			_										
	ь Ч К												
			-	-									
	0 0												
	00		-	-									
			30-										
					IXI	22-37-50/4"				5.2			
	0 0				$\langle - \rangle$								
2	00		_										
	b Ž												
			-	1									
	2												
			-	1									
			25										
	60 t		35–		\times	50/5"				10.5			
	000		_										
	0												
			_										
	O		-										
		39 N											
		CLAYSTONE, tan, drv, fine-grained, moderately	1 -										
	$\rangle\rangle$	fractured, close fracture spacing, thin bedding, highly weathered, weak rock, trace of gravel and sand	40-										
4	\mathbb{Z}	weathered, weak rock, trace of graver and sand	40		$\mathbb{N}/$	10-10-26							
	\mathbb{K}		_		X	N=36				25.1			
	$\langle X \rangle$	41.5 Boring Terminated at 41.5 Feet	ł		\leftarrow		-						
		Boring Terminated at 41.5 Feet											
See	Explor	ation and Testing Procedures for a description of field and laboratory		w	ater	Level Observation	ns					Drill Rig	
prod	cedures	used and additional data (If any).				None						BK-81	
See	Suppo	rting Information for explanation of symbols and abbreviations.				Observed						Hammer Typ Automatic	е
Ni					die-	comont Matter d						Driller Haztech / P. B	ray
Not		Pafaranca: Flavations were obtained from Google Forth			dvan SA	cement Method							
rie/	ימנוטח א	Reference: Elevations were obtained from Google Earth										Logged by TJ Trussell	
												Boring Starte	ed
						onment Method backfilled with auge	ar cutt	ings upo	n com	letion		02-14-2023	
				ВС	Ji ii iy	backimed with adge	or cutt	iiiga upo	ii comp	ACCIOII.		Boring Comp	leted
												02-14-2023	




_													
ér	og	Location: See Exploration Plan	÷	ان الآ	be	it	St	rength 1	Test	(%	t cf)	Atterberg Limits	
Model Layer	Graphic Log	Latitude: 44.5117° Longitude: -109.0820° Depth (Ft.)	Depth (Ft.)	Water Level Observations	Sample Type	Field Test Results	Test Type	Compressive Strength (psf)	Strain (%)	Water Content (%)	Dry Unit Weight (pcf)	LL-PL-PI	
		WELL GRADED GRAVEL WITH SILT AND SAND (GW-GM), fine grained, subangular, brown, moist, medium dense to dense, homogeneous	_	-	X	6-8-9 N=17				12.3			
			_	-	X	14-22-19 N=41				3.6			
1	00000		5-	-		10-11-12				2.3			
			_	-		N=23							
		9.0 POORLY GRADED GRAVEL WITH SILT AND SAND (GP-GM), with cobbles, coarse grained, subrounded,	_	-	X	14-16-16 N=32				2.7			
		brown, dry, very dense, homogeneous	10-	-	X	15-50/4"				3.2			
			_	-									
			15-	-	X	23-50/5"				3.1			
2			_	-									
			20-	-									
				_	\times	50/5"							
			- -	-									
	2		25-										
pro	cedures	ation and Testing Procedures for a description of field and laboratory used and additional data (If any). rting Information for explanation of symbols and abbreviations.		W		Level Observation None Observed	ıs					Drill Rig BK-81 Hammer Typ	e
Not					dvan SA	cement Method						Automatic Driller Haztech / P. B	iray
Ele	vation F	Reference: Elevations were obtained from Google Earth		A	band	onment Method backfilled with auge	er cutt	ings upo	n comp	oletion.		Logged by TJ Trussell Boring Starte 02-15-2023	
												Boring Comp 02-15-2023	ieted



Г. П		Location: See Exploration Plan			-		C+	rength 7	Γρςt			Atterberg	
aye.	Log	Latitude: 44.5117° Longitude: -109.0820°	F	evel	Type	est Its		_		er : (%)	nit (pcf)	Limits	
Model Layer	Graphic Log	Depth (Ft.)	Depth (Ft.)	Water Level Observations	Sample Type	Field Test Results	Test Type	Compressive Strength (psf)	Strain (%)	Water Content (%)	Dry Unit Weight (pcf)	LL-PL-PI	
		POORLY GRADED GRAVEL WITH SILT AND SAND (GP-GM), with cobbles, coarse grained, subrounded, brown, dry, very dense, homogeneous (continued)	_		X	16-15-27 N=42				5.9			
			_										
			_										
			-										
			30-										
			-			20-50/5"				6.2			
			-										
2			-										
			-										
			35-			18-28-33				F 4			
			-			N=61				5.1			
			-										
			_										
			40-										
		41.0	140		X	21-26-20 N=46				5.8			
4	Σ	41.5 CLAYSTONE , tan, dry, fine-grained, moderately fractured, close fracture spacing, thin bedding, highly weathered, weak rock, trace of gravel and sand											
		Boring Terminated at 41.5 Feet											
See	Explora	ation and Testing Procedures for a description of field and laboratory		W	/ater	Level Observation	ıs					Drill Rig	
prod	cedures	used and additional data (If any). rting Information for explanation of symbols and abbreviations.				None Observed						Hammer Type	e
												Automatic Driller Haztech / P. B	rav
Not Elev		Reference: Elevations were obtained from Google Earth			dvan SA	cement Method						Logged by TJ Trussell	iay
				А	band	onment Method						Boring Starte 02-15-2023	ed
						backfilled with auge	r cutt	ings upo	n comp	oletion.		Boring Comp 02-15-2023	leted









			1	1									1
er	bc	Location: See Exploration Plan	_	<u>~</u> &	pe d	يب	St	rength 1	Гest	(%)	[(Atterberg Limits	
Model Layer	Graphic Log	Latitude: 44.5116° Longitude: -109.0818°	Depth (Ft.)	Water Level Observations	Sample Type	Field Test Results	ā	Compressive Strength (psf)	(0)	Water Content (%)	Dry Unit Weight (pcf)		
e 	phi	Latitude: 44.5110 Longitude: -105.0010	£	erL	ble	nsə pi	Test Type	sssi gth f)	Strain (%)	Vat	y L		
Jod	ìra		de	Vat	am	ë a	St	ren (psi	ain	> ino	/eig	LL-PL-PI	
2	0	Donah (Ft.)		>0	0)		Te	St	Str	0	>		
	ه ک از ا	Depth (Ft.) POORLY GRADED GRAVEL WITH SILT AND SAND						O					
		(GP-GM), with cobbles, coarse grained, subrounded,			V	28-36-43				4.2			
	0.0	brown, dry, very dense, homogeneous (continued)	-		A	N=79				7.2			
	Co Co		_	1									
	0												
			_										
	0 0		30-										
	0				\times	41-50/4"				4.5			
	。 <mark>(</mark>		_	1									
	o 🕒 🔻												
	0		-	1									
2													
			-	1									
	0												
			-	1									
			35-	1	~	50/1"							
	o (1)												
	0												
	o 💆 🧲		_										
	CO CO												
	0		_										
			_	_									
	• A •	40.2	40-		><	50/2"				5.4			
		Boring Terminated at 40.2 Feet				30/2				J.4.			
				1	,	Laval Classic							
See	Explora	ation and Testing Procedures for a description of field and laboratory used and additional data (If any).		W		Level Observation	15					Drill Rig BK-81	
		rting Information for explanation of symbols and abbreviations.				None Observed							
	Sappoi					Obset ved						Hammer Typ Automatic	e
												Driller	
Not	AC			Α.	dvan	cement Method						Haztech / P. B	Bray
		Reference: Elevations were obtained from Google Earth			avan SA	cement Method							
LIEV	acion R	Actoremee. Elevations were obtained from Google Earth										Logged by TJ Trussell	
												Boring Starte	ed
						onment Method	ar cutt	ings upo	n com-	aletica		02-15-2023	
				В	uiiig	backfilled with auge	- cutt	mys upo	ii comp	netion.		Boring Comp	leted
												02-15-2023	











_													
ë	bc	Location: See Exploration Plan		ا ا ا	be	<u>.</u>	St	rength 1	Γest	(%)	cf)	Atterberg Limits	
Model Layer	Graphic Log	Latitude: 44.5118° Longitude: -109.0819°	Depth (Ft.)	Water Level Observations	Sample Type	Field Test Results	e	ع د	(%)	Water Content (%)	Dry Unit Weight (pcf)		
lel	phi	Latitude: 44.3110 Longitude: 107.0017	Ę	erL	ıρle	. pla	Тур	essi ngth if)	%) ر	Nat ten	ry L ght		
Moc	Gra		Эер	Wat Obse	San	Fi R	Test Type	npre trer (ps	Strain (%)	Con	Nei	LL-PL-PI	
-		Depth (Ft.)					🛎	Compressive Strength (psf)	St				
	0 7.5	WELL GRADED GRAVEL WITH SAND (GW), fine			/								
	10 (M)	grained, subangular, brown, moist, medium dense to dense, homogeneous	_		IXI	5-6-5 N=11				13.5			
	0 0	dense, nomogeneous			$\langle \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \$								
			_										
	000		-		$ \bigvee $	7-11-11				4.3			
	lo ()				$ \Lambda $	N=22				4.3			
	0 0		-										
	6 C		_										
1	B		5-										
'	JOC		_		X	30-30-18 N=48				4.1			
	[(\ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \				\triangle								
	0.0		-										
	b X C						-						
	P 🔆		-	ł	$ \bigvee $	14-33-50/5"				3.6			
					$/\backslash$	2.33.30,3				5.5			
			-	1			1						
	Po		10-										
	$^{\circ}$	11.0	10-		$\setminus /$								
		11.0	-		X	23-46-50/5"				2.9		NP	
		POORLY GRADED GRAVEL WITH SILT AND SAND (GP-GM), with cobbles, coarse grained, subrounded,			\sim								
		brown, dry, very dense, homogeneous, auger refusal	-										
	O	at 18 feet											
	000		-										
	0												
	b C		-	-									
2	6		15-										
			15		\bigvee	41-50/5"				3.6			
	0		_	-	\vdash	, -							
	00												
	b Q C		-	-									
		18.0											
	- · N·	Auger Refusal at 18 Feet	-										
		_											
See	Explor	ation and Testing Procedures for a description of field and laboratory		w	ater	Level Observation	าร					Drill Rig	
prod	cedures	used and additional data (If any).			- 1	None						BK-81	
See	Suppo	rting Information for explanation of symbols and abbreviations.				Observed						Hammer Typ	е
												Automatic	
												Driller Haztech / P. B	rav
Not		Deforming Flouriting were abtained from County Facts			dvan SA	cement Method							-/
Elev	vation F	Reference: Elevations were obtained from Google Earth										Logged by TJ Trussell	
												Boring Starte	ed
						onment Method	or cutt	inge une	n com-	lation		02-13-2023	
				BC	oring	backfilled with auge	er cutt	mgs upo	ii comp	лецоп.		Boring Comp	leted
												02-14-2023	



See Earloration From 1 Testing Proposition Fig. Someth Test Someth T	Layer Cayer Layer Layer	·		_ o	ı oo l		Ju	ungui l	COL		6.7		
Depth (R.) Depth	— <u>.=</u> Lautude:	44 5116° Longitude: -109 0806°	Ĥ.	eve.	Typ	Fest Ilts				er t (%	Jnit (pcf	Limits	
Depth (R.) Depth	aph	44.3116 · Longitude109.0606	pth (ater L	mple	ield 1 Resu	Тур	ressiv ingth isf)	in (%	Wat _i ntent	ory U	I I -PI -PT	
WELL GRADE GRAVE WITH SLIT AND SAND TOOLUNG detire it is define, floring-investors Very dense Very dense 10- 3-1-19-12 8-10-16 8-10-16 8-10-16 8-23-22-18 8-47 23-22-18 8-40 29 23-22-18 8-40 29 23-22-18 8-40 29 23-25-18 8-40 20 23-22-18 8-40 20 23-25-18 8-40 20 23-25-18 8-40 20 20 21-18-12 23-22-18 8-40 20 20 21-18-18-18-18-18-18-18-18-18-18-18-18-18			De	×ão	Sa	ш.	Test	omp Stre (p	Stra	Co	We		
medium dense to dense, homogeneous 8:10-16 N=28 23-22-18 N=40 29 29 Very dense 50 See Exploration and Testine Procedures for a description of field and laboratory procedures used and additional data (if any). See Supporting Information for explanation of symbols and abbreviations. Notes Elevation Reference: Elevations were obtained from Google Earth Advancement Method 15M Notes Elevation Reference: Elevations were obtained from Google Earth Advancement Method 15M Notes Advancement Method 15M Advancement Method 15M Loggad by L	o	L GRADED GRAVEL WITH SILT AND SAND				11-10-12		0					
Neez Exploration and Testing Procedures for a description of field and laboratory procedures used and additional data (I amy). See Exploration and Testing Procedures for a description of field and laboratory procedures used and additional data (I amy). See Supporting Information for explanation of symbols and abbreviations. Notes Elevation Reference: Elevations were obtained from Google Earth Advancement Method Inc. 81 Advancement Method Inc. 81 Inc	med	ium dense to dense, homogeneous	_		X	N=31				9.6			
Neez Exploration and Testing Procedures for a description of field and laboratory procedures used and additional data (I amy). See Exploration and Testing Procedures for a description of field and laboratory procedures used and additional data (I amy). See Supporting Information for explanation of symbols and abbreviations. Notes Elevation Reference: Elevations were obtained from Google Earth Advancement Method Inc. 81 Advancement Method Inc. 81 Inc			_										
N=26 N=26 Solvery dense Very dense Very dense Solvery dense	Pool		_			0 10 16							
very dense very d					X	N=26				4.7			
very dense very dense very dense solution and Testing Procedures for a description of field and laboratory procedures used and additional data (If any). See Exploration and Testing Procedures for a description of field and laboratory procedures used and additional data (If any). See Supporting Information for explanation of symbols and abbreviations. Notes Bievation Reference: Elevations were obtained from Google Earth Advancement Method ISA			_										
very dense 10 23-50/3* 2.5 8oring Terminated at 10.8 Feet 10 23-50/4* 2.1 23-50/4* 2.1 See Exploration and Testing Procedures for a description of field and laboratory procedures used and additional data (If any). See Supporting Information for explanation of symbols and abbreviations. Notes Notes Reference: Elevations were obtained from Google Earth Advancement Method 15A Advancement Method 15A 10 2.5 2.5 Drill Rig IK-81 Particle / P. Bray Logged by 15 Truckell	1		5 –			22 22 10							
See Exploration and Testing Procedures for a description of field and laboratory procedures used and additional data (if any). See Supporting Information for explanation of symbols and abbreviations. Water Level Observations None Observed Mammare Type Automatic Drille Notes Elevation Reference: Elevations were obtained from Google Earth Advancement Method 15.4 Advancement Method 15.4 Logged by 17 Triuscell			_	-	X	N=40				2.9			
See Exploration and Testing Procedures for a description of field and laboratory procedures used and additional data (if any). See Supporting Information for explanation of symbols and abbreviations. Water Level Observations None Observed Mammare Type Automatic Drille Notes Elevation Reference: Elevations were obtained from Google Earth Advancement Method 15.4 Advancement Method 15.4 Logged by 17 Triuscell			_										
See Exploration and Testing Procedures for a description of field and laboratory procedures used and additional data (If any). See Supporting Information for explanation of symbols and abbreviations. Notes Elevation Reference: Elevations were obtained from Google Earth 23-50/4* 21. Water Level Observations None Observed Advancement Method ISA Advancement Method ISA 17 Trussell	very	dense	_		\times	50/5"				2.5			
See Exploration and Testing Procedures for a description of field and laboratory procedures used and additional data (If any). See Supporting Information for explanation of symbols and abbreviations. Notes Elevation Reference: Elevations were obtained from Google Earth 23-50/4* 21. Water Level Observations None Observed Advancement Method ISA Advancement Method ISA 17 Trussell	200												
See Exploration and Testing Procedures for a description of field and laboratory procedures used and additional data (If any). See Supporting Information for explanation of symbols and abbreviations. Notes Elevation Reference: Elevations were obtained from Google Earth 23-50/4* 21. Water Level Observations None Observed Advancement Method ISA Advancement Method ISA 17 Trussell			_										
See Exploration and Testing Procedures for a description of field and laboratory procedures used and additional data (if any). See Supporting Information for explanation of symbols and abbreviations. Water Level Observations None Observed Hammer Type Automatic Priller Hammer Type Automatic Priller Harten (F. P. Bray). Notes Elevation Reference: Elevations were obtained from Google Earth Advancement Method Hish Advancement Method Logged by 17 Trussell			10-			23-50/4"				2.1			
procedures used and additional data (If any). See Supporting Information for explanation of symbols and abbreviations. Observed Hammer Type Automatic Driller Notes Elevation Reference: Elevations were obtained from Google Earth Advancement Method HSA Logged by TJ Trussell		ing Terminated at 10.8 Feet											
procedures used and additional data (If any). See Supporting Information for explanation of symbols and abbreviations. Observed Hammer Type Automatic Driller Haztech / P. Bray Elevation Reference: Elevations were obtained from Google Earth None BK-81 Advancement Method HSA Logged by TJ Trussell													
procedures used and additional data (If any). See Supporting Information for explanation of symbols and abbreviations. Observed Hammer Type Automatic Driller Haztech / P. Bray Elevation Reference: Elevations were obtained from Google Earth None BK-81 Advancement Method HSA Logged by TJ Trussell													
procedures used and additional data (If any). See Supporting Information for explanation of symbols and abbreviations. Observed Hammer Type Automatic Driller Haztech / P. Bray Elevation Reference: Elevations were obtained from Google Earth None BK-81 Advancement Method HSA Logged by TJ Trussell													
procedures used and additional data (If any). See Supporting Information for explanation of symbols and abbreviations. Observed Hammer Type Automatic Driller Haztech / P. Bray Elevation Reference: Elevations were obtained from Google Earth None BK-81 Advancement Method HSA Logged by TJ Trussell													
procedures used and additional data (If any). See Supporting Information for explanation of symbols and abbreviations. Observed Hammer Type Automatic Driller Haztech / P. Bray Elevation Reference: Elevations were obtained from Google Earth None BK-81 Advancement Method HSA Logged by TJ Trussell													
procedures used and additional data (If any). See Supporting Information for explanation of symbols and abbreviations. Observed Hammer Type Automatic Driller Haztech / P. Bray Elevation Reference: Elevations were obtained from Google Earth None BK-81 Advancement Method HSA Logged by TJ Trussell													
procedures used and additional data (If any). See Supporting Information for explanation of symbols and abbreviations. Observed Hammer Type Automatic Driller Haztech / P. Bray Elevation Reference: Elevations were obtained from Google Earth None BK-81 Advancement Method HSA Logged by TJ Trussell													
procedures used and additional data (If any). See Supporting Information for explanation of symbols and abbreviations. Observed Hammer Type Automatic Driller Haztech / P. Bray Elevation Reference: Elevations were obtained from Google Earth None BK-81 Advancement Method HSA Logged by TJ Trussell													
procedures used and additional data (If any). See Supporting Information for explanation of symbols and abbreviations. Observed Hammer Type Automatic Driller Haztech / P. Bray Elevation Reference: Elevations were obtained from Google Earth None BK-81 Advancement Method HSA Logged by TJ Trussell													
procedures used and additional data (If any). See Supporting Information for explanation of symbols and abbreviations. Observed Hammer Type Automatic Driller Haztech / P. Bray Elevation Reference: Elevations were obtained from Google Earth None BK-81 Advancement Method HSA Logged by TJ Trussell													
procedures used and additional data (If any). See Supporting Information for explanation of symbols and abbreviations. Observed Hammer Type Automatic Driller Haztech / P. Bray Elevation Reference: Elevations were obtained from Google Earth None BK-81 Advancement Method HSA Logged by TJ Trussell													
procedures used and additional data (If any). See Supporting Information for explanation of symbols and abbreviations. Observed Hammer Type Automatic Driller Haztech / P. Bray Elevation Reference: Elevations were obtained from Google Earth None BK-81 Advancement Method HSA Logged by TJ Trussell													
procedures used and additional data (If any). See Supporting Information for explanation of symbols and abbreviations. Observed Hammer Type Automatic Driller Haztech / P. Bray Elevation Reference: Elevations were obtained from Google Earth None BK-81 Advancement Method HSA Logged by TJ Trussell													
procedures used and additional data (If any). See Supporting Information for explanation of symbols and abbreviations. Observed Hammer Type Automatic Driller Haztech / P. Bray Elevation Reference: Elevations were obtained from Google Earth None BK-81 Advancement Method HSA Logged by TJ Trussell													
procedures used and additional data (If any). See Supporting Information for explanation of symbols and abbreviations. Observed Hammer Type Automatic Driller Haztech / P. Bray Elevation Reference: Elevations were obtained from Google Earth None BK-81 Advancement Method HSA Logged by TJ Trussell													
procedures used and additional data (If any). See Supporting Information for explanation of symbols and abbreviations. Observed Hammer Type Automatic Driller Haztech / P. Bray Elevation Reference: Elevations were obtained from Google Earth None BK-81 Advancement Method HSA Logged by TJ Trussell													
procedures used and additional data (If any). See Supporting Information for explanation of symbols and abbreviations. Observed Hammer Type Automatic Driller Haztech / P. Bray Elevation Reference: Elevations were obtained from Google Earth None BK-81 Advancement Method HSA Logged by TJ Trussell													
See Supporting Information for explanation of symbols and abbreviations. Observed Hammer Type Automatic Driller Haztech / P. Bray HSA Logged by TJ Trussell	See Exploration and I	Festing Procedures for a description of field and laboratory additional data (If any).		W			ıs					Drill Rig BK-81	
Notes Reference: Elevations were obtained from Google Earth Advancement Method HSA Logged by TJ Trussell												Hammer Typ	e
Notes Elevation Reference: Elevations were obtained from Google Earth Advancement Method HSA Logged by TJ Trussell													
Elevation Reference: Elevations were obtained from Google Earth T] Trussell						cement Method						Haztech / P. B	ray
Roring Started	Elevation Reference:	Elevations were obtained from Google Earth			_, (TJ Trussell	
Abandonment Method 02-17-2023				A	band	onment Method						Boring Starte 02-17-2023	ed
Boring backfilled with auger cuttings upon completion. Boring Completed				В	oring	backfilled with auge	r cutt	ngs upo	n comp	letion.		Boring Comp 02-17-2023	leted



_													
er	29	Location: See Exploration Plan	_	<u>~ ~</u>	oe Oe	t	St	rength ⁻	Test	(%	cf)	Atterberg Limits	
Model Layer	Graphic Log	Latitude: 44.5112° Longitude: -109.0806°	Depth (Ft.)	Water Level Observations	Sample Type	Field Test Results	pe	is di	(%	Water Content (%)	Dry Unit Weight (pcf)		
odel	raph		epth	/ater	ampl	Field	Test Type	oress engt psf)	Strain (%)	Wa	Dry eigh	LL-PL-PI	
ĮΣ	ַ <u>ত</u>	Depth (Ft.)	Ĭ	≥¤	Š	_	Tes	Compressive Strength (psf)	Stra	ا ٽ	>		
		SANDY FAT CLAY (CH), medium to high plasticity,				9-11-8							
		brown, moist, very stiff	-	-	X	N=19				12.2			
3													
			-			9-12-17 N=29				11.2			
		4.0	_		\triangle	N-29							
	600	WELL GRADED GRAVEL WITH SILT AND SAND (GW-GM), fine grained, subangular, brownish tan,	_										
	00	dry, very dense, homogeneous	5-			20 25 50/5"				2.4			
	600		-		Λ	28-35-50/5"				2.4			
	000		_										
1	600												
	000		-	İ	X	11-23-50/5"				3.0			
	[O		_	ł			-						
	600		10-										
	600	10.8	10-		\times	24-50/4"				1.8			
		Boring Terminated at 10.8 Feet											
L													
Se	Explor	ation and Testing Procedures for a description of field and laboratory		W		Level Observation	าร					Drill Rig BK-81	
		used and additional data (If any). rting Information for explanation of symbols and abbreviations.				None Observed						BK-81 Hammer Typ	•
												Automatic	_
	to.				d. · · ·	coment Matter						Driller Haztech / P. B	ray
	tes vation f	Reference: Elevations were obtained from Google Earth			avan SA	cement Method						Logged by	
				Al	band	onment Method backfilled with auge	ar cutt	inge uno	n com	nlation		Boring Starte 02-17-2023	sa
				D	ornig	backimed with auge	i cutt	mys upo	ii comp	JIELIUII.		Boring Comp 02-17-2023	leted



SANDY TAT CLAY (CH). medium to high plasticity, brown, most, self to very stiff Solvery Constitution of the property of the p				Ι	1					_			Atterberg	
SARDY FAT CLAY (CH), medium to high plasticity, brown, mast, stiff to very deff strong, mast, stiff to very define, brongeneous strong, sty, strongeneous	yer	Log	Location: See Exploration Plan	t.	/el	ype	s		_		(%)	it pcf)	Limits	
SARDY FAT CLAY (CH), medium to high plasticity, brown, mast, stiff to very deff strong, mast, stiff to very define, brongeneous strong, sty, strongeneous	el La	hic	Latitude: 44.5112° Longitude: -109.0808°	h (F	r Le	Je T	d Te	уре	ssive Jth	(%)	ater ent (y Un ht (¡		
SARDY FAT CLAY (CH), medium to high plasticity, brown, mast, stiff to very deff strong, mast, stiff to very define, brongeneous strong, sty, strongeneous	Mode	Grap		Cept	Wate Obse	Samp	Fiel	st T	treng (psf	rain	Cont	Dr. Veig	LL-PL-PI	
Solution Reference: Elevations were obtained from Google Earth Abandonment Nethod Boring Terminated at 10-4 Feet Abandonment Nethod Rock Reference: Elevations were obtained from Google Earth Abandonment Nethod Boring Started Abandonment Nethod Boring Started Abandonment Nethod Boring Started Boring Boring Star	Ĺ		Depth (Ft.)			Ĺ		Ţ	Con	St				
See Exporation and Testing Procedures for a description of field and laboratory precedures used and additional data (if any). See Supporting Information for explanation of symbols and abbreviations. Notes Notes Clevation Reference: Elevations were obtained from Google Earth Notes Clevation Reference: Elevations were obtained from Google Earth Notes Clevation Reference: Elevations were obtained from Google Earth Notes Notes Advancement Method Resigned Control of Control			SANDY FAT CLAY (CH), medium to high plasticity, brown, moist, stiff to very stiff			\mathbb{N}	5-7-8				14 0			
See Exploration and Testring Procedures for a description of field and laboratory procedures used and additional data (if any). See Exploration and Testring Procedures for a description of field and laboratory procedures used and additional data (if any). See Exploration and Testring Procedures for a description of field and laboratory procedures used and additional data (if any). See Exploration for explanation of symbols and abbreviations. Notes Advancement Method Bring hast/filled with augur cuttings upon completion. Boring Terminated at 10.4 Feet Water Level Observations Note Observed Advancement Method Bring hast/filled with augur cuttings upon completion. Bring Completed Oct. 7-20.73 Bri			, ,	-	1	$\backslash \backslash$	N=15				14.0			
See Exploration and Testring Procedures for a description of field and laboratory procedures used and additional data (if any). See Exploration and Testring Procedures for a description of field and laboratory procedures used and additional data (if any). See Exploration and Testring Procedures for a description of field and laboratory procedures used and additional data (if any). See Exploration for explanation of symbols and abbreviations. Notes Advancement Method Bring hast/filled with augur cuttings upon completion. Boring Terminated at 10.4 Feet Water Level Observations Note Observed Advancement Method Bring hast/filled with augur cuttings upon completion. Bring Completed Oct. 7-20.73 Bri				-										
See Exploration and Testing Denodures for a description of field and laboratory procedures used and additional class (If any). See Supporting Information for explanation of symbols and abbreviations. Nates Nates Advancement Method Boring Started Corp. 72, 203 Boring Started Corp. 72, 203 Boring Started Corp. 72, 203 Bring Completion. Notes Abandonment Method Boring backfilled with aggre cuttings upon completion. Boring Started Corp. 72, 203 Boring Started Corp. 203 Boring Completed Corp. 203 Boring Started Corp. 203 Boring Started Corp. 203 Boring Started Corp. 203 Boring Completed Corp. 203 Boring	3													
WELL GRAPE GRAVEL WITH SILT AND SAND (Gw.GM), fine grained, subangular brown, dry, dense to very dense, hornogeneous 10-16-19-17 N=36 Boring Terminated at 10.4 Feet 10-150/5* 3.6 See Exploration and Tetting Procedures for a description of field and laboratory procedures used and additional data (if any). See Exploration and Tetting Procedures for a description of field and laboratory procedures used and additional data (if any). See Exploration for explanation of symbols and abbreviations. Notes Notes Advancement Method Bring Started Boring				-		IX	8-7-7 N=14				15.0			
WELL GRAPE GRAVEL WITH SILT AND SAND (Gw.GM), fine grained, subangular brown, dry, dense to very dense, hornogeneous 10-16-19-17 N=36 Boring Terminated at 10.4 Feet 10-150/5* 3.6 See Exploration and Tetting Procedures for a description of field and laboratory procedures used and additional data (if any). See Exploration and Tetting Procedures for a description of field and laboratory procedures used and additional data (if any). See Exploration for explanation of symbols and abbreviations. Notes Notes Advancement Method Bring Started Boring				-	-									
16-19-17 N=36 4.0				5-										
dense to very dense, homogeneous 10 22-43-50/5* 2.9 20-43-50/5* 3.6 See Exploration and Testing Procedures for a description of field and laboratory procedure used and additional data (if any). See Exploration and Testing Procedures for a description of field and laboratory procedure used and additional data (if any). See Supporting Information for explanation of symbols and abbreviations. Water Level Observations None Observed Advancement Method Bring Started Output Drill Rig Br- 61 Hammer Type Automatic Drill Rig Br- 61 Advancement Method Bring Started Oz.17-2023 Boring Completed		600	(GW-GM), fine grained, subangular, brown, dry,				16-19-17				4.0			
See Exploration and Testing Procedures for a description of field and laboratory procedures used and additional data (If any). See Supporting Information for explanation of symbols and abbreviations. Water Level Observations None Observed Advancement Method Birning Started O2:17-2023 Boring Completed		00	dense to very dense, homogeneous	-			N=36							
See Exploration and Testing Procedures for a description of field and laboratory procedures used and additional data (If any). See Supporting Information for explanation of symbols and abbreviations. Water Level Observations None Observed Advancement Method Birning Started O2:17-2023 Boring Completed		000		_										
See Exploration and Testing Procedures for a description of field and laboratory procedures used and additional data (If any). See Supporting Information for explanation of symbols and abbreviations. Water Level Observations None Observed Advancement Method HisA Abandonment Method Boring Started O2:17-2023 Boring Completed	1	Pop				7								
See Exploration and Testing Procedures for a description of field and laboratory procedures used and additional data (If any). See Supporting Information for explanation of symbols and abbreviations. Notes Elevation Reference: Elevations were obtained from Google Earth Water Level Observations None Observed Observed Advancement Method HSA Abandonment Method Boring backfilled with auger cuttings upon completion. Boring Started Oct. 17-2023 Boring Started Oct. 17-2023 Boring Started Oct. 17-2023 Boring Started Oct. 17-2023 Boring Completed		000				X	22-43-50/5"				2.9			
See Exploration and Testing Procedures for a description of field and laboratory procedures used and additional data (If any). See Supporting Information for explanation of symbols and abbreviations. Notes Elevation Reference: Elevations were obtained from Google Earth Water Level Observations None Observed Observed Advancement Method HSA Abandonment Method Boring backfilled with auger cuttings upon completion. Boring Started Oct. 17-2023 Boring Started Oct. 17-2023 Boring Started Oct. 17-2023 Boring Started Oct. 17-2023 Boring Completed		000		-										
See Exploration and Testing Procedures for a description of field and laboratory procedures used and additional data (If any). See Supporting Information for explanation of symbols and abbreviations. Notes Elevation Reference: Elevations were obtained from Google Earth Water Level Observations None Observed Observed Advancement Method HSA Abandonment Method Boring backfilled with auger cuttings upon completion. Boring Started Oct. 17-2023 Boring Started Oct. 17-2023 Boring Started Oct. 17-2023 Boring Started Oct. 17-2023 Boring Completed		000	10.4	10-			FO/F"				2.6			
procedures used and additional data (If any). See Supporting Information for explanation of symbols and abbreviations. Observed Advancement Method HSA Abandonment Method Boring backfilled with auger cuttings upon completion. BK-81 Hammer Type Automatic Driller Haztech / P. Bray Logged by TJ Trussell Boring Started 02-17-2023 Boring Completed	Г	1) -[[1			50/5				3.6			
procedures used and additional data (If any). See Supporting Information for explanation of symbols and abbreviations. Observed Advancement Method HSA Abandonment Method Boring backfilled with auger cuttings upon completion. BK-81 Hammer Type Automatic Driller Haztech / P. Bray Logged by TJ Trussell Boring Started 02-17-2023 Boring Completed														
procedures used and additional data (If any). See Supporting Information for explanation of symbols and abbreviations. Observed Advancement Method HSA Abandonment Method Boring backfilled with auger cuttings upon completion. BK-81 Hammer Type Automatic Driller Haztech / P. Bray Logged by TJ Trussell Boring Started 02-17-2023 Boring Completed														
procedures used and additional data (If any). See Supporting Information for explanation of symbols and abbreviations. Observed Advancement Method HSA Abandonment Method Boring backfilled with auger cuttings upon completion. BK-81 Hammer Type Automatic Driller Haztech / P. Bray Logged by TJ Trussell Boring Started 02-17-2023 Boring Completed														
procedures used and additional data (If any). See Supporting Information for explanation of symbols and abbreviations. Observed Advancement Method HSA Abandonment Method Boring backfilled with auger cuttings upon completion. BK-81 Hammer Type Automatic Driller Haztech / P. Bray Logged by TJ Trussell Boring Started 02-17-2023 Boring Completed														
procedures used and additional data (If any). See Supporting Information for explanation of symbols and abbreviations. Observed Advancement Method HSA Abandonment Method Boring backfilled with auger cuttings upon completion. BK-81 Hammer Type Automatic Driller Haztech / P. Bray Logged by TJ Trussell Boring Started 02-17-2023 Boring Completed														
procedures used and additional data (If any). See Supporting Information for explanation of symbols and abbreviations. Observed Advancement Method HSA Abandonment Method Boring backfilled with auger cuttings upon completion. BK-81 Hammer Type Automatic Driller Haztech / P. Bray Logged by TJ Trussell Boring Started 02-17-2023 Boring Completed														
procedures used and additional data (If any). See Supporting Information for explanation of symbols and abbreviations. Observed Advancement Method HSA Abandonment Method Boring backfilled with auger cuttings upon completion. BK-81 Hammer Type Automatic Driller Haztech / P. Bray Logged by TJ Trussell Boring Started 02-17-2023 Boring Completed														
procedures used and additional data (If any). See Supporting Information for explanation of symbols and abbreviations. Observed Advancement Method HSA Abandonment Method Boring backfilled with auger cuttings upon completion. BK-81 Hammer Type Automatic Driller Haztech / P. Bray Logged by TJ Trussell Boring Started 02-17-2023 Boring Completed														
procedures used and additional data (If any). See Supporting Information for explanation of symbols and abbreviations. Observed Advancement Method HSA Abandonment Method Boring backfilled with auger cuttings upon completion. BK-81 Hammer Type Automatic Driller Haztech / P. Bray Logged by TJ Trussell Boring Started 02-17-2023 Boring Completed														
procedures used and additional data (If any). See Supporting Information for explanation of symbols and abbreviations. Observed Advancement Method HSA Abandonment Method Boring backfilled with auger cuttings upon completion. BK-81 Hammer Type Automatic Driller Haztech / P. Bray Logged by TJ Trussell Boring Started 02-17-2023 Boring Completed														
procedures used and additional data (If any). See Supporting Information for explanation of symbols and abbreviations. Observed Advancement Method HSA Abandonment Method Boring backfilled with auger cuttings upon completion. BK-81 Hammer Type Automatic Driller Haztech / P. Bray Logged by TJ Trussell Boring Started 02-17-2023 Boring Completed														
procedures used and additional data (If any). See Supporting Information for explanation of symbols and abbreviations. Observed Advancement Method HSA Abandonment Method Boring backfilled with auger cuttings upon completion. BK-81 Hammer Type Automatic Driller Haztech / P. Bray Logged by TJ Trussell Boring Started 02-17-2023 Boring Completed														
procedures used and additional data (If any). See Supporting Information for explanation of symbols and abbreviations. Observed Advancement Method HSA Abandonment Method Boring backfilled with auger cuttings upon completion. BK-81 Hammer Type Automatic Driller Haztech / P. Bray Logged by TJ Trussell Boring Started 02-17-2023 Boring Completed														
procedures used and additional data (If any). See Supporting Information for explanation of symbols and abbreviations. Observed Advancement Method HSA Abandonment Method Boring backfilled with auger cuttings upon completion. BK-81 Hammer Type Automatic Driller Haztech / P. Bray Logged by TJ Trussell Boring Started 02-17-2023 Boring Completed														
procedures used and additional data (If any). See Supporting Information for explanation of symbols and abbreviations. Observed Advancement Method HSA Abandonment Method Boring backfilled with auger cuttings upon completion. BK-81 Hammer Type Automatic Driller Haztech / P. Bray Logged by TJ Trussell Boring Started 02-17-2023 Boring Completed														
procedures used and additional data (If any). See Supporting Information for explanation of symbols and abbreviations. Observed Advancement Method HSA Abandonment Method Boring backfilled with auger cuttings upon completion. BK-81 Hammer Type Automatic Driller Haztech / P. Bray Logged by TJ Trussell Boring Started 02-17-2023 Boring Completed														
procedures used and additional data (If any). See Supporting Information for explanation of symbols and abbreviations. Observed Advancement Method HSA Abandonment Method Boring backfilled with auger cuttings upon completion. BK-81 Hammer Type Automatic Driller Haztech / P. Bray Logged by TJ Trussell Boring Started 02-17-2023 Boring Completed														
procedures used and additional data (If any). See Supporting Information for explanation of symbols and abbreviations. Observed Advancement Method HSA Abandonment Method Boring backfilled with auger cuttings upon completion. BK-81 Hammer Type Automatic Driller Haztech / P. Bray Logged by TJ Trussell Boring Started 02-17-2023 Boring Completed														
procedures used and additional data (If any). See Supporting Information for explanation of symbols and abbreviations. Observed Advancement Method HSA Abandonment Method Boring backfilled with auger cuttings upon completion. BK-81 Hammer Type Automatic Driller Haztech / P. Bray Logged by TJ Trussell Boring Started 02-17-2023 Boring Completed														
procedures used and additional data (If any). See Supporting Information for explanation of symbols and abbreviations. Observed Advancement Method HSA Abandonment Method Boring backfilled with auger cuttings upon completion. BK-81 Hammer Type Automatic Driller Haztech / P. Bray Logged by TJ Trussell Boring Started 02-17-2023 Boring Completed	L													
See Supporting Information for explanation of symbols and abbreviations. Observed Observed Hammer Type Automatic Driller Haztech / P. Bray HSA Abandonment Method Boring backfilled with auger cuttings upon completion. Boring Completed	Sec	e Explor	ation and Testing Procedures for a description of field and laboratory used and additional data (If any).	,	W			ıs					Drill Rig BK-81	
Notes Elevation Reference: Elevations were obtained from Google Earth Abandonment Method Boring backfilled with auger cuttings upon completion. Boring Completed													Hammer Typ	e
Notes Elevation Reference: Elevations were obtained from Google Earth Abandonment Method Boring backfilled with auger cuttings upon completion. Advancement Method Boring backfilled with auger cuttings upon completion. Bactech / P. Bray Logged by TJ Trussell Boring Started 02-17-2023 Boring Completed														
Elevation Reference: Elevations were obtained from Google Earth Abandonment Method Boring backfilled with auger cuttings upon completion. Boring Completed	No	tes					cement Method							ray
Abandonment Method Boring backfilled with auger cuttings upon completion. Boring Completed			Reference: Elevations were obtained from Google Earth										Logged by	
Abandonment Method Boring backfilled with auger cuttings upon completion. Boring Completed													Boring Starte	ed
Boring Completed								er cutt	ings upo	n comp	oletion.		02-17-2023	
						J	, and the second			·			Boring Comp 02-17-2023	leted



Location: See Exploration Plan Latitude: 44.5111° Longitude: -109.0816° Depth (Ft.) SANDY FAT CLAY (CH), medium to high plasticity, brown, moist, stiff Output (bb) Output (bc) Output
Depth (Ft.) SANDY FAT CLAY (CH), medium to high plasticity, brown, moist, stiff UC 1708 1.2 16.3 106 50-22-28
Depth (Ft.) SANDY FAT CLAY (CH), medium to high plasticity, brown, moist, stiff UC 1708 1.2 16.3 106 50-22-28
Depth (Ft.) SANDY FAT CLAY (CH), medium to high plasticity, brown, moist, stiff UC 1708 1.2 16.3 106 50-22-28
SANDY FAT CLAY (CH), medium to high plasticity, brown, moist, stiff UC 1708 1.2 16.3 106 50-22-28
N=11
5 - 4-5-4 13.0
7.5
WELL GRADED GRAVEL WITH SILT AND SAND (GW-GM), fine grained, subangular, brown, dry, very
dense, homogeneous Caw-GM
1 0 0 9
21-23-31 N=54 4.1
Boring Terminated at 11.5 Feet
Borning Terminated at 11.5 Feet
See Evolution and Testing Procedures for a description of field and laboratory Water Level Observations Drill Rig
procedures used and additional data (If any). None BK-81
See Exploration and resting Procedures for a description of field and laboratory
procedures used and additional data (If any). See Supporting Information for explanation of symbols and abbreviations. Observed Hammer Typ Automatic Driller
procedures used and additional data (If any). See Supporting Information for explanation of symbols and abbreviations. Observed Hammer Type Automatic Driller Notes Advancement Method
procedures used and additional data (If any). See Supporting Information for explanation of symbols and abbreviations. None Observed Hammer Type Automatic Priller
procedures used and additional data (If any). See Supporting Information for explanation of symbols and abbreviations. None Observed Hammer Tyr Automatic Driller Haztech / P. E Elevation Reference: Elevations were obtained from Google Earth Advancement Method HSA Logged by T) Trussell Boring Start
procedures used and additional data (If any). See Supporting Information for explanation of symbols and abbreviations. Observed Hammer Typ Automatic Driller Haztech / P. E Elevation Reference: Elevations were obtained from Google Earth Advancement Method HSA Logged by TJ Trussell



			I						_			Atterberg	
yer	Log	Location: See Exploration Plan	t.	/el	ype	s	St	rength ⁻		(%)	it pcf)	Limits	
Model Layer	Graphic Log	Latitude: 44.5109° Longitude: -109.0816°	Depth (Ft.)	Water Level Observations	Sample Type	Field Test Results	Test Type	Compressive Strength (psf)	Strain (%)	Water Content (%)	Dry Unit Weight (pcf)	LL-PL-PI	
		Depth (Ft.) SANDY FAT CLAY (CH), medium to high plasticity, brown, moist, stiff	_		X	7-9-6 N=15		ŭ		13.0			
3			_		SN)								
3			_		X	6-7-7 N=14				12.1			
	601	5.5 WELL GRADED GRAVEL WITH SILT AND SAND	5 –		\bigvee	5-14-49				15.5			
		(GW-GM), fine grained, subangular, brown, dry, very dense, homogeneous	_			N=63							
1			_		X	25-34-36 N=70				2.8			
			10-										
	200	11.4 Boring Terminated at 11.4 Feet	_		\triangle	12-25-50/5"				3.5		NP	
pro	cedures	ation and Testing Procedures for a description of field and laboratory used and additional data (If any). rting Information for explanation of symbols and abbreviations.	W	-	Level Observation None Observed	is					Drill Rig BK-81 Hammer Typ Automatic	e	
A.	•					annuant Mart						Driller Haztech / P. B	ray
	tes vation F	Reference: Elevations were obtained from Google Earth		Advancement Method HSA							Logged by TJ Trussell	-,	
						lonment Method backfilled with auge	er cutt	ings upo	n comp	oletion.		Boring Starte 02-16-2023 Boring Comp 02-16-2023	



		1	1						1			
ē	Location: See Exploration Plan		_ s	be	4	St	ength 1	Гest	(%)	(5	Atterberg Limits	
Model Layer	Latitude: 44.5120° Longitude: -109.0825°	Depth (Ft.)	Water Level Observations	Sample Type	Field Test Results	e	Compressive Strength (psf)	(0)	Water Content (%)	Dry Unit Weight (pcf)		
Je :		£	ter L	nple	ple	Test Type	essi ngth sf)	Strain (%)	Wat	ry l	II DI DI	
Moc	2	Dep	Wa	Sar	<u> </u>	est	npr trei (ps	raii	Con	Wei	LL-PL-PI	
	Depth (Ft.)					-	Cor	ß				
0	SILTY GRAVEL WITH SAND (GM), fine grained,			\setminus	7 7 12							
51	subangular to subrounded, brown, moist to dry, medium dense	_		IXI	7-7-13 N=20				10.1			
[9				$\langle \ \ \rangle$								
0		-	1									
l P	<u>.</u> 3.											
0	<u>}</u>	-	1	V	6-6-4				4.5			
1 0				$ /\rangle$	N=10				5			
9	<u>.9.1</u>	-										
0		5-										
]		$\mathbb{N}/$	6-6-6							
0): <u>(</u>	-	-	IXI	N=12				3.3			
0												
19		-	1									
6	POORLY GRADED GRAVEL WITH SILT AND SAND	1										
0	(GP-GM), with cobbles, coarse grained, subrounded,	-	1	X	14-16-19 N=35				3.2			
6	light brown, dry, very dense to dense, homogeneous	_		$\langle \cdot \rangle$	N-33							
0	(a)											
		10-	4									
		-		$ \vee $	18-26-32 N=58				2 2			
0	a contract of the contract of	-	-	$ \Lambda $	N=58				3.2			
6	<u>.a.</u>											
0		-	1									
)_(
2		-										
0		_										
2	. <mark></mark>											
0		15-	1									
6					15-17-25				3.1			
2	. <mark>.0.</mark> .	-	1	$ \Lambda $	N=42				3.1			
	No.											
		-	1									
0												
0												
0	<u>) </u>	-										
0												
5	7.0	20-	1									
6				$ \bigvee $	24-19-15				4.7			
0	21.5	_	Ĺ	$/\backslash$	N=34	L		L	L'''			
	Boring Terminated at 21.5 Feet											
			1									
	ploration and Testing Procedures for a description of field and laboratory ures used and additional data (If any).	4	W		Level Observation None	15					Drill Rig BK-81	
	pporting Information for explanation of symbols and abbreviations.			None Observed						Hammer Typ	•	
					33301700						Automatic	-
											Driller	
Notes					cement Method						Haztech / P. B	ray
	on Reference: Elevations were obtained from Google Earth			SA							Logged by TJ Trussell	
			Boring Started Abandonment Method 02-16-2023					ed				
			Boring backfilled with auger cuttings upon completion.					lat- I				
		Boring Complete 02-16-2023					retea					



e go	Location: See Exploration Plan	_	_ g	be	4	St	ength 1	Гest	(%)	(5	Atterberg Limits	
Model Layer Graphic Log	Latitude: 44.5120° Longitude: -109.0928°	Depth (Ft.)	Water Level Observations	Sample Type	Field Test Results	e	Compressive Strength (psf)	(%)	Water Content (%)	Dry Unit Weight (pcf)		
lel Phi		th	terl	nple	ple	Test Type	essi ngth sf)	Strain (%)	Wat	ry l ght		
Mod		Dep	Wai	San	i <u>≅</u> &	est	npr trer (ps	rair	Con	Λei	LL-PL-PI	
	Depth (Ft.)					Ĕ	Con	ss				
0 7.	SILTY GRAVEL WITH SAND (GM), fine grained,			\ /	6 12 12							
84	subangular to subrounded, brown, moist to dry, medium dense	_		IXI	6-12-12 N=24				9.4			
	: mediam derise											
		-										
_o O		-	1	$ \vee $	7-7-5				2.8			
1 6 0				$ \Lambda $	N=12				2.0			
P P		-	1									
67		5-										
54	<u> </u>	5-			7-10-20							
		_		X	N=30				4.6			
0												
9.0	·	_	-									
	7.5 POORLY GRADED GRAVEL WITH SILT AND SAND	1				-						
	(GP-GM), with cobbles, coarse grained, subrounded,	-	1	$ \bigvee $	21-26-39				2.7			
0	light brown, dry, very dense to dense, homogeneous			$/\backslash$	N=65				,			
6		-	1									
S O		10-										
	i de la companya de	10		\mathbb{N}								
		_		IXI	23-29-50/5"				3.7			
0 Q		-	-									
6 6												
		-										
	-											
1 9		-	1									
2	<u>.</u>	15-										
[o (<u>)</u> •		13		\mathbb{N}	31-50/5"				3.1			
		_		\vdash	, -							
6 <mark>2</mark> 9												
		-										
	,											
		-	1									
o 🗨 🤇		-	1									
6		20-]									
	· •	20		$\mathbb{N}/$	49-27-16							
100	21.5	-	4	X	N=43							
	21.5 Boring Terminated at 21.5 Feet	1	<u></u>	\vdash								
.	Johns Terminated at 21.5 1 eet											
See Explo	ration and Testing Procedures for a description of field and laboratory		W	/ater	Level Observation	าร					Drill Rig	
procedure	s used and additional data (If any).		-	None						BK-81		
See Supp	orting Information for explanation of symbols and abbreviations.				Observed						Hammer Typ	e
											Automatic	
											Driller Haztech / P. B	irav
Notes					cement Method							u y
∟levation	Reference: Elevations were obtained from Google Earth		HSA Logged by TJ Trussell						TJ Trussell			
			Boring Started					ed				
			Abandonment Method 02-16-2023					-				
		Boring backfilled with auger cuttings upon completion. Boring Completed 02-16-2023										
											02-16-2023	



			1	1						1		Albert	
ē	od	Location: See Exploration Plan	$\overline{}$	س م	be		St	ength 1	Γest	(%	l le	Atterberg Limits	
Model Layer	Graphic Log	Latitude: 44.5122° Longitude: -109.0822°	Depth (Ft.)	Water Level Observations	Sample Type	Field Test Results	be	Compressive Strength (psf)	(%	Water Content (%)	Dry Unit Weight (pcf)		
del	aph		pth	ater	mple	Res	Τχ	ress ngtl sf)	₀) u	Wa	Z igh	LL-PL-PI	
ω	Ğ		De	 Sq	Sal	Œ -	Test Type	Stre (p	Strain (%)	Co	We		
		Depth (Ft.)			L.,			o°;	5				
0	1	<u>SILTY GRAVEL WITH SAND (GM)</u> , fine grained, subangular to subrounded, brown, moist to dry, loose				8-8-8				7.			
þ	3	to medium dense	-	-	$ \Lambda $	N=16				7.6			
0													
0			-										
1 /	7 9					F 2 4							
0	M.				X	5-2-4 N=6				4.3		NP	
þ	345		_										
0	9 (
0		5.0 POORLY GRADED GRAVEL WITH SILT AND SAND	5 –	_									
ŀ		(GP-GM), with cobbles, coarse grained, subrounded,			X	6-5-6							
- [4		light brown, dry, dense to very dense, homogeneous	_		$V \setminus$	N=11							
			_										
و													
0	0		-	-		18-16-18				22			
ŀ						N=34				3.3			
2			-	1									
0			10										
<u> </u>			10-	1		11-23-41							
0			_		IXI	N=64				3.4		NP	
ŀ													
2			_										
0													
2			-	_									
٥	O		_										
ŀ													
		hand drilling from 15 20 feet	15-	-									
٥		hard drilling from 15-20 feet				21-26-30				2.8			
Ď			-	_	$ \wedge $	N=56				2.0			
0	0												
ŀ			_										
7			_										
P	0												
<u> </u>			-	_									
6	Ot												
ŀ		medium dense	20-	1									
					X	13-8-7 N=15				6.0			
°	7	21.5			\angle	20							
		Boring Terminated at 21.5 Feet											
See F	Explor	ation and Testing Procedures for a description of field and laboratory		W	/ater	Level Observation	ıs					Drill Rig	
proce	edures	used and additional data (If any).				None						BK-81	
See S	Suppo	rting Information for explanation of symbols and abbreviations.				Observed						Hammer Typ	е
												Automatic	
Net					 .	aamant Mathad						Driller Haztech / P. B	ray
Note		Reference: Elevations were obtained from Google Earth			dvan SA	cement Method						Logged by	
Lieva	acioii l	Acid chee. Lievations were obtained from 600gle Editif							TJ Trussell				
				Boring Started					ed				
				Abandonment Method Boring backfilled with auger cuttings upon completion. Baring Completes									
				,			_ ,				Boring Comp 02-16-2023	leted	




			1							-	A.L. 1	
er og	Location: See Exploration Plan	-	<u>_</u> &	be	يب	St	rength 1	Test	(%	l G	Atterberg Limits	
Model Layer Graphic Log	Latitude: 44.5122° Longitude: -109.0819°	Depth (Ft.)	Water Level Observations	Sample Type	Field Test Results	ā	ه ر	(0)	Water Content (%)	Dry Unit Weight (pcf)		
phi	Latitude: 44.3122 Longitude: 103.0013	Ę	erL	Jple	nsa.	Гур	essi ngth f)	8	Vat ten	ry L ght		
Moc 3ra)ep	Wat)bse	San	Fi R	Test Type	hpr Frer (ps	Strain (%)	700	Veig	LL-PL-PI	
- -	Depth (Ft.)					"	Compressive Strength (psf)	St		>		
0 7.1	SILTY GRAVEL WITH SAND (GM), fine grained,			/								
600	subangular to subrounded, brown, moist to dry, medium dense			ΙXΙ	7-9-10 N=19				22.3			
9.9	medium dense			$V \setminus$	N-19							
67		l _										
54												
		_	_	$\mathbb{N}/$	7-7-5							
l on				IXI	N=12				7.5			
1		-		\sim								
6 Q (
(C		5 –	_									
9.9				V	4-6-6							
67		-	1	/	N=12							
514												
	7.5	-	1									
000	POORLY GRADED GRAVEL WITH SILT AND SAND				11 11 10							
le di	(GP-GM), with cobbles, coarse grained, subrounded, light brown, dry, medium dense to very dense,			X	11-11-18 N=29				2.8			
0.0	homogeneous	_	1	$\angle \setminus$								
600												
<u></u>		10-	-									
b 🔾					18-34-50/2"				8.1			
l 6		-		\angle								
0:0												
		-	-									
0.0		_										
2		_										
		15-										
0 00		13		$\mathbb{N}/$	12-12-14							
0 : D		_	_	IXI	N=26				3.3			
0 2.0				\sim								
		-										
0:0												
		-	+									
		-	1									
[• 6		20										
0.0		20-	1		22 22 22	1						
lo 💆 🤇		l .		X	32-23-22 N=45				2.5			
6 6	21.5			m m m m m m m m m m m m m								
	Boring Terminated at 21.5 Feet											
	ration and Testing Procedures for a description of field and laboratory sused and additional data (If any).	W		Level Observation	15					Drill Rig BK-81		
	orting Information for explanation of symbols and abbreviations.				None Observed							
то сирр	2				ODSEI VEU						Hammer Typ Automatic	e
											Driller	
Notes			A	dvan	cement Method						Haztech / P. B	ray
	Reference: Elevations were obtained from Google Earth			SA							Logged by	
			T) Truss					Logged by TJ Trussell				
			Abandonment Method					Boring Starte 02-16-2023	ed			
			Boring backfilled with auger cuttings upon completion.									
		Boring Complete 02-16-2023					leted					
											JZ 10 ZUZJ	



Atterberg Limit Results

ASTM D4318




	Boring ID	Depth (Ft)	LL	PL	PI	Fines	USCS	Description
•	B-10	0 - 1.5	35	24	11	31.0	SC	CLAYEY SAND
×	B-12	10 - 11.4	NP	NP	NP	3.2	GW	WELL-GRADED GRAVEL with SAND
	B-8	5 - 6.5	NP	NP	NP	7.6	GW-GM	WELL-GRADED GRAVEL with SILT and SAND
*	P-10	10 - 11.4	NP	NP	NP	8.5	GW-GM	WELL-GRADED GRAVEL with SILT and SAND
•	P-9	2.5 - 4.5	50	22	28	58.1	CH	SANDY FAT CLAY
٠	RW-3	2.5 - 4	NP	NP	NP	12.5	GM	SILTY GRAVEL with SAND
0	RW-3	10 - 11.5	NP	NP	NP	5.5	GP-GM	POORLY GRADED GRAVEL with SILT and SAND



Grain Size Distribution


ASTM D422 / ASTM C136



ierracon 2110 Overland Ave Ste 124 Billings, MT


Grain Size Distribution

ASTM D422 / ASTM C136





Swell Consolidation TestASTM D2435




	Boring ID	Depth (Ft)	Description	uscs	$\gamma_{\rm d(pcf)}$	WC (%)					
•	P-9	2.5 - 4.5	SANDY FAT CLAY	СН	107	16.3					
	N + 0 - 1 + 1 + 1 + 1 + 1 + 1 + 1 + 1 + 1 + 1										

Notes: Sample inundated at 1000 psf



Unconsolidated-Undrained Test ASTM D2850



Boring ID	Depth (Ft)	Sample type	LL	PL	ΡI	Fines (%)	Description
P-9	2.5 - 4.5	Shelby Tube	50	22	28	58.1	SANDY FAT CLAY(CH)

	Boring ID	Depth (Ft)	Sample type	LL	PL	ΡI	Fines (%)	Description
	P-9	2.5 - 4.5	Shelby Tube	50	22	28	58.1	SANDY FAT CLAY(CH)
Specimen Failure Mode								Specimen Test Data

1			
	9	indicate the second	

Specimen	Test Data
Moisture Content (%):	16.3
Dry Density (pcf)	106.3
Diameter (in):	2.86
Height (in):	5.17
Height / Diameter Ratio:	1.81
Calculated Saturation (%)	
Calculated Void Ratio:	
Assumed Specific Gravity:	
Failure Strain (%):	1.16
Compressive Strength (psf):	1708
Undrained Shear Strength (psf):	854
Strain Rate (in/min):	
Cell Pressure (psi):	
Remarks:	



ANALYTICAL SUMMARY REPORT

March 08, 2023

Terracon Consultants 2110 Overland Ave Ste 124 Billings, MT 59102-6440

Work Order: B23021678 Quote ID: B5647

Project Name: Cody Site

Energy Laboratories Inc Billings MT received the following 1 sample for Terracon Consultants on 2/28/2023 for analysis.

Lab ID	Client Sample ID	Collect Date	Receive Date	Matrix	Test
B23021678-001	RW-3 2.5-4		02/28/23	Soil	Anions, Saturated Paste Extract pH, Saturated Paste Saturated Paste Extraction ASA Resistivity, Sat Paste

The analyses presented in this report were performed by Energy Laboratories, Inc., 1120 S 27th St., Billings, MT 59101, unless otherwise noted. Any exceptions or problems with the analyses are noted in the report package. Any issues encountered during sample receipt are documented in the Work Order Receipt Checklist.

The results as reported relate only to the item(s) submitted for testing. This report shall be used or copied only in its entirety. Energy Laboratories, Inc. is not responsible for the consequences arising from the use of a partial report.

Date: 2023.03.08 12:17:37 -07:00

If you have any questions regarding these test results, please contact your Project Manager.

Digitally signed by Sonya Mallett
Soil Department Supervisor Date: 2023.03 08 1

Report Approved By:

Page 1 of 7





LABORATORY ANALYTICAL REPORT

Prepared by Billings, MT Branch

Client: Terracon Consultants

 Project:
 Cody Site

 Lab ID:
 B23021678-001

 Client Sample ID:
 RW-3 2.5-4

Report Date: 03/08/23
Collection Date: Not Provided
DateReceived: 02/28/23

Matrix: Soil

Analyses	Result	Units	Qualifiers	RL	MCL/ QCL	Method	Analysis Date / By
SATURATED PASTE EXTRACT							
Resistivity, Sat. Paste	407	ohm-cm		1		Calculation	03/07/23 16:02 / srm
pH, sat. paste	7.5	s.u.		0.1		ASA10-3	03/07/23 16:02 / srm
Sulfate	1090	mg/L		1		E300.0	03/07/23 17:36 / caa

Report RL - Analyte Reporting Limit

Definitions: QCL - Quality Control Limit

MCL - Maximum Contaminant Level

ND - Not detected at the Reporting Limit (RL)





QA/QC Summary Report

Prepared by Billings, MT Branch

Client: Terracon Consultants Work Order: B23021678 **Report Date:** 03/08/23

Analyte		Count	Result	Units	RL	%REC Lo	ow Limit	High Limit	RPD	RPDLimit	Qual
Method:	ASA10-3									Batch:	R398607
Lab ID:	B23021657-001A DUF	P San	nple Duplica	ate		R	un: MISC-	SOIL_230307B		03/07/	/23 16:02
pH, sat. pa	aste		8.20	s.u.	0.10				1.2	10	
Lab ID:	LCS-2303071602	Lab	oratory Con	trol Sample		R	un: MISC-	SOIL_230307B		03/07/	/23 16:02
pH, sat. pa	aste		7.10	s.u.	0.10	95	90	110			



QA/QC Summary Report

Prepared by Billings, MT Branch

Client: Terracon Consultants Work Order: B23021678 Report Date: 03/08/23

Analyte	Co	unt Result	Units	RL	%REC Lo	w Limit H	ligh Limit	RPD	RPDLimit	Qual
Method:	Calculation								Batch:	R398607
Lab ID:	B23021657-001A DUP	Sample Duplic	cate		Ru	n: MISC-SC	DIL_230307B		03/07/	/23 16:02
Resistivity,	Sat. Paste	1980	ohm-cm	1.0		70	130	4.1	30	
Lab ID:	LCS-2303071602	Laboratory Co	ontrol Sample		Ru	n: MISC-SC	OIL_230307B		03/07/	/23 16:02
Resistivity,	Sat. Paste	190	ohm-cm	1.0	89	70	130			



QA/QC Summary Report

Prepared by Billings, MT Branch

Client: Terracon Consultants Work Order: B23021678 Report Date: 03/08/23

Analyte		Count	Result	Units	RL	%REC	Low Limit	High Limit	RPD	RPDLimit	Qual
Method:	E300.0									Batcl	n: 176542
Lab ID:	LCS-176542	Lab	oratory Cor	ntrol Sample			Run: IC ME	TROHM 2_230	306A	03/07/	23 17:19
Sulfate			2040	mg/L	2.0	102	70	130			
Lab ID:	B23021678-001AMS	San	nple Matrix	Spike			Run: IC ME	TROHM 2_230	306A	03/07/	23 17:53
Sulfate			2210	mg/L	1.1	112	70	130			
Lab ID:	B23030259-001ADUF	San	nple Duplic	ate			Run: IC ME	TROHM 2_230	306A	03/07/	/23 19:00
Sulfate			24.0	mg/L	1.0				3.0	30	

Work Order Receipt Checklist

Terracon Consultants

Login completed by: Lyndsi F. LeProwse

B23021678

Login completed by:	Lyndsi E. LeProwse		Date	Received: 2/28/2023
Reviewed by:	gmccartney		Re	eceived by: lel
Reviewed Date:	3/3/2023		Cai	rrier name: Hand Deliver
Shipping container/cooler in	good condition?	Yes	No 🗌	Not Present ✓
Custody seals intact on all s	hipping container(s)/cooler(s)?	Yes	No 🗌	Not Present 🗸
Custody seals intact on all sa	ample bottles?	Yes	No 🗌	Not Present 🗸
Chain of custody present?		Yes ✓	No 🗌	
Chain of custody signed who	en relinquished and received?	Yes ✓	No 🗌	
Chain of custody agrees with	n sample labels?	Yes ✓	No 🗌	
Samples in proper container	/bottle?	Yes ✓	No 🗌	
Sample containers intact?		Yes ✓	No 🗌	
Sufficient sample volume for	indicated test?	Yes ✓	No 🗌	
All samples received within h (Exclude analyses that are c such as pH, DO, Res CI, Su	onsidered field parameters	Yes √	No 🗌	
Temp Blank received in all s	hipping container(s)/cooler(s)?	Yes	No 🔽	Not Applicable
Container/Temp Blank tempe	erature:	19.1°C No Ice		
Containers requiring zero he bubble that is <6mm (1/4").	adspace have no headspace or	Yes	No 🗌	No VOA vials submitted
Water - pH acceptable upon	receipt?	Yes	No 🗌	Not Applicable 🔽

Standard Reporting Procedures:

Lab measurement of analytes considered field parameters that require analysis within 15 minutes of sampling such as pH, Dissolved Oxygen and Residual Chlorine, are qualified as being analyzed outside of recommended holding time.

Solid/soil samples are reported on a wet weight basis (as received) unless specifically indicated. If moisture corrected, data units are typically noted as -dry. For agricultural and mining soil parameters/characteristics, all samples are dried and ground prior to sample analysis.

The reference date for Radon analysis is the sample collection date. The reference date for all other Radiochemical analyses is the analysis date. Radiochemical precision results represent a 2-sigma Total Measurement Uncertainty.

Contact and Corrective Action Comments:

None

Chain of Custody & Analytical Request Record

Account Information (Billing information)	rmation (Billing	information)		96	Report	t Informat	ion (if diff	Report Information (if different than Account Information)	unt Information)		Com	Comments	
Company/Name Torocon	-	Consultants	.0		Company/Name	/Name	Same	os left	7				
Contact Nattelney	7	222			Contact					P-			
Phone 466-493	3	0			Phone	and the second			- Opini				
Mailing Address	13th	Ave SW			Mailing Address	ddress							
City. State, Zip		MI	HO465		City, State, Zip	ə, Zip		The state of					
Email Motshew. Hoffmann @ Lerra can, Cem	v. Hoffmann	@tennian	Com		Email			ا د ا د					
Receive Invoice	Hard Copy. DEME	iail Receive Rep	Receive Report	/ Æmail	Receive F	Receive Report. Hard Copy		□Email					
26,33500 4	Quote		Bottle Order		Special Report	Special Report/Formats:		EDD/EDT (contact laboratory)	ratory) 🗆 Other				
Project Information	nation				Matrix Codes	sepo		Ans	Analysis Requested	sted			
Project Name, PWSID, Permit, etc.	ID, Permit, etc.	Lody Site	le.		W- Water	ater			3 .1			All	All turnaround times are standard unless marked as
Sampler Name		Sampler Phone	эс	â I	S S		_) (c)		- 6		RUSH.
Sample Origin State		EPA/State Compliance	ompliance	oN 🗆 se	V - Vegetation B - Bioassav	9 8	ht					MUS.	Energy Laboratories MUST be contacted prior to
Lab provided preservatives were used		□ Yes □ No		4.3	O - Other		r(,4				pə		RUSH sample submittal for
MINING CLIENTS, please indicate sample type. "If ore has been processed or refined, call before sending. Byproduct 11 (e)2 material	ease indicate sample essed or refined, call I	mple type. call before sending. ☐ Unprocessed ore (NOT ground or refined)*	NOT ground or rei	ined)*	DW - Drinking Water		5100 1105/				Attach	5	See Instructions Page
Sar	Sample Identification	ation etc.)	Colle	Collection	Number of Containers (Matrix Pt		TH	1		995	RUSH	ELI LAB ID Laboratory Use Only
1 RW-3 125-	25-40				_	a	• ^					83	820112050
2									110				
m					, ,		J. 10	-				14	
4						- A	Section 1		7 8	4		R	
vo.				1 4 BO						i i		7	
9	12												
6 m 2	C WANTE OF THE	Walter Hart		N 917 5	×				2		0	-	
8						3	F-3						
o	No. Harris	A The Atlant								7			
10		A PART WAY		12 (12 m)	The Property of	1 500 1	E I	X.			8		
	(pript)	1	Date/Time	Signature Signature	True 1	111	0	Received by (print)		Date/Time	62	Signature	
be signed Rel	Relinquished by (print)	(Xen)	Date/Time	1.27	nature	c mo	Ž.	Repeived by Laboratory (print)	Spory (print)	Date/Time /53	bh: 51 8	Signature	li Lehounze
Shipped By	Cooler ID(s)	Custody Seals	Intact	Receipt Temp	p Temp Blank	NA N	On Ice		Payment Type	Amount \$	R	ceipt Numbe	Receipt Number (cash/check only)
		מ כ ב				1			CIGCA				

In certain circumstances, samples submitted to Energy Laboratories, Inc. may be subcontracted to other certified laboratories in order to complete the analysis requested.

This serves as notice of this possibility. All subcontracted data will be clearly notated on your analytical report.

ELI-COC-06/08 v.2

Supporting Information

Contents:

General Notes Unified Soil Classification System Description of Rock Properties

Note: All attachments are one page unless noted above.



General Notes

Sampling	Water Level		Field Tests
Grab Shelby Sample Tube	 ✓ Water Initially Encountered ✓ Water Level After a Specified Period of Time 	N (HP)	Standard Penetration Test Resistance (Blows/Ft.) Hand Penetrometer
Split Spoon	Water Level After a Specified Period of Time	(T)	Torvane
	Cave In Encountered		Dynamic Cone Penetrometer
	Water levels indicated on the soil boring logs are the levels measured in the borehole at the times indicated.	UC	Unconfined Compressive Strength
	Groundwater level variations will occur over time. In low permeability soils, accurate determination of	(PID)	Photo-Ionization Detector
	groundwater levels is not possible with short term water level observations.	(OVA)	Organic Vapor Analyzer

Descriptive Soil Classification

Soil classification as noted on the soil boring logs is based Unified Soil Classification System. Where sufficient laboratory data exist to classify the soils consistent with ASTM D2487 "Classification of Soils for Engineering Purposes" this procedure is used. ASTM D2488 "Description and Identification of Soils (Visual-Manual Procedure)" is also used to classify the soils, particularly where insufficient laboratory data exist to classify the soils in accordance with ASTM D2487. In addition to USCS classification, coarse grained soils are classified on the basis of their in-place relative density, and fine-grained soils are classified on the basis of their consistency. See "Strength Terms" table below for details. The ASTM standards noted above are for reference to methodology in general. In some cases, variations to methods are applied as a result of local practice or professional judgment.

Location And Elevation Notes

Exploration point locations as shown on the Exploration Plan and as noted on the soil boring logs in the form of Latitude and Longitude are approximate. See Exploration and Testing Procedures in the report for the methods used to locate the exploration points for this project. Surface elevation data annotated with +/- indicates that no actual topographical survey was conducted to confirm the surface elevation. Instead, the surface elevation was approximately determined from topographic maps of the area.

(More than 50% reta	F Coarse-Grained Soils ained on No. 200 sieve.) andard Penetration Resistance		Consistency of Fine-Grained Soil (50% or more passing the No. 200 sie mined by laboratory shear strength test procedures or standard penetration resis	ve.) ing, field visual-manual
Relative Density	Standard Penetration or N-Value (Blows/Ft.)	Consistency	Unconfined Compressive Strength Qu (tsf)	Standard Penetration or N-Value (Blows/Ft.)
Very Loose	0 - 3	Very Soft	less than 0.25	0 - 1
Loose	4 - 9	Soft	0.25 to 0.50	2 - 4
Medium Dense	10 - 29	Medium Stiff	0.50 to 1.00	4 - 8
Dense	30 - 50	Stiff	1.00 to 2.00	8 - 15
Very Dense	> 50	Very Stiff	2.00 to 4.00	15 - 30
		Hard	> 4.00	> 30

Strength Terms

Relevance of Exploration and Laboratory Test Results

Exploration/field results and/or laboratory test data contained within this document are intended for application to the project as described in this document. Use of such exploration/field results and/or laboratory test data should not be used independently of this document.

Temple at the Nielson Site | Cody, Wyoming March 28, 2023 | Terracon Project No. 26235004



Unified Soil Classification System

Criteria for As	ssianina Group	Symbols and G	roup Names Using	Soi	I Classification
			roup numeo comg	Group Symbol	Group Name B
	Gravels:	Clean Gravels:	Cu≥4 and 1≤Cc≤3 ^E	GW	Well-graded gravel F
	More than 50% of	Less than 5% fines ^c	Cu<4 and/or [Cc<1 or Cc>3.0] E	GP	Poorly graded gravel F
	coarse fraction retained on No. 4	Gravels with Fines	Fines classify as ML or MH	GM	Silty gravel F, G, H
Coarse-Grained Soils:	sieve	More than 12% fines ^c	Fines classify as CL or CH	GC	Clayey gravel F, G, H
More than 50% retained on No. 200 sieve		Clean Sands:	Cu≥6 and 1≤Cc≤3 ^E	SW	Well-graded sand ^I
	Sands: 50% or more of	Less than 5% fines D	Cu<6 and/or [Cc<1 or Cc>3.0] E	nes classify as ML or MH nes classify as CL or CH 7 and plots above "A" line J SP Poorly graded sand I SIlty sand G, H, I Clayey sand G, H, I Lean clay K, L, M	
	Sands: 50% or more of coarse fraction passes No. 4 sieve Sands with Fines: More than 12% fines D Cu<6 and/or [Cc<1 or Cc>3.0] E Fines classify as ML or MH SM Silty sand G, H, I Fines classify as CL or CH SC Clayey sand G, H, I Clayey sand G, H, I Silty sand G, H, I Fines classify as CL or CH SC Clayey sand G, H, I	Silty sand G, H, I			
	passes its. I sieve	Clean Sands: Less than 5% fines D Cu<6 and/or [Cc<1 or Cc>3.0] E SP Poorly graded sand I Sieve Sands with Fines: More than 12% fines D Fines classify as ML or MH SM Silty sand G, H, I Fines classify as CL or CH SC Clayey sand G, H, I PI > 7 and plots above "A" line J PI < 4 or plots below "A" line J ML Silt K, L, M Silt K, L, M			
		Ingrania	PI > 7 and plots above "A" line ³	CL	Lean clay K, L, M
	Silts and Clays: Liquid limit less than	inorganic:	PI < 4 or plots below "A" line ³	ML	Silt K, L, M
	50	Organica	$\frac{LL \ oven \ dried}{LL \ not \ dried} < 0.75$	OL	Organic clay K, L, M, N
Fine-Grained Soils: 50% or more passes the		Organic.	LL not dried < 0.75	OL	Organic silt K, L, M, O
No. 200 sieve		Inorganic	PI plots on or above "A" line	CH	Fat clay ^{K, L, M}
	Silts and Clays: Liquid limit 50 or	Inorganic.	PI plots below "A" line	MH	Elastic silt K, L, M
	more	Organica	LL oven dried	ОН	Organic clay K, L, M, P
		Less than 5% fines C Gravels with Fines: More than 12% fines C Clean Sands: Less than 5% fines D Sands with Fines: More than 12% fines D Inorganic: Gravels with Fines: More than 12% fines D Inorganic: Inorganic: Inorganic:	$\frac{LL \text{ over arrea}}{LL \text{ not dried}} < 0.75$	OH	Organic silt ^{K, L, M, Q}
Highly organic soils:	Primarily o	Clean Sands: Less than 5% fines D Sands with Fines: Nore than 12% fines D Inorganic: Organic: Organic: Organic:	color, and organic odor	PT	Peat


- A Based on the material passing the 3-inch (75-mm) sieve.
- B If field sample contained cobbles or boulders, or both, add "with cobbles or boulders, or both" to group name.
- Gravels with 5 to 12% fines require dual symbols: GW-GM well-graded gravel with silt, GW-GC well-graded gravel with clay, GP-GM poorly graded gravel with silt, GP-GC poorly graded gravel with clay.
- P Sands with 5 to 12% fines require dual symbols: SW-SM well-graded sand with silt, SW-SC well-graded sand with clay, SP-SM poorly graded sand with silt, SP-SC poorly graded sand with clay.

E Cu =
$$D_{60}/D_{10}$$
 Cc = $\frac{(D_{30})^2}{D_{10} \times D_{60}}$

- $^{\mathsf{F}}$ If soil contains ≥ 15% sand, add "with sand" to group name.
- ^G If fines classify as CL-ML, use dual symbol GC-GM, or SC-SM.

- H If fines are organic, add "with organic fines" to group name.
- If soil contains ≥ 15% gravel, add "with gravel" to group name.
- J If Atterberg limits plot in shaded area, soil is a CL-ML, silty clay.

 K If soil contains 15 to 29% plus No. 200, add "with sand" or
- K If soil contains 15 to 29% plus No. 200, add "with sand" or "with gravel," whichever is predominant.
- $^{\text{L}}$ If soil contains \geq 30% plus No. 200 predominantly sand, add "sandy" to group name.
- M If soil contains ≥ 30% plus No. 200, predominantly gravel, add "gravelly" to group name.
- N PI ≥ 4 and plots on or above "A" line.
- PI < 4 or plots below "A" line.
- P PI plots on or above "A" line.
- Q PI plots below "A" line.



Temple at the Nielson Site | Cody, Wyoming March 28, 2023 | Terracon Project No. 26235004



Rock Classification Notes

Term

Fresh		tals appear bright; show no discolor end into intact rock.	ation. Features show little or now st	aining on surfaces. Discolora	ation		
Slightly weathered	Rock genera rock.	lly fresh except along fractures. Sor	ne fractures stained and discoloration	n may extend <0.5 inches i	nto		
Moderately weathered		ortions of rock are dull and discolor oil zones of limited extent may occur	ed. Rock may be significantly weake r along some fractures.	r than in fresh state near			
Highly weathered		d discolored throughout. Majority of d; isolated zones of stronger rock ar	rock mass is significantly weaker and/or soil may occur throughout.	nd has decomposed and/or			
Completely weathered		erial is decomposed and/or disintegr es of stronger rock may occur locall	rated to soil. The rock mass or fabrio y.	c is still evident and largely i	intact.		
		STRENGTH O	R HARDNESS				
Description		Field Identi	fication	Uniaxial Compro Strength, p			
Extremely strong	•		ock rings on hammer blows. Canno quire several hard hammer blows to	> 36 000			
Very strong		rs of a geological hammer to fracture el nail. Can be scratched with a geo		15,000-36,00	00		
Strong	20d nail or g	eologist's pick. Gouges or grooves	ded to fracture. Can be scratched w to ¼ inch deep can be excavated by s can be detached by a moderate blo	7,500-15,00	0		
Medium strong	nail. Can be point. Can b	grooved or gouged 1/16 in. deep by e fractured with single firm blow of	re. Can be distinctly scratched with firm pressure with a geologist's pic geological hammer. Can be excavate blows of the point of a geologist's p	k ed in 3,500-7,500	0		
Weak	readily with	geologist's pick point. Can be excav	mer point. Can be gouged or groov ated in pieces several inches in size es can be broken by finger pressure	by 700-3,500			
Very weak	the point of	obles under firm blow with geological hammer point. Can be excavated readily with oint of a geologist's pick. Pieces 1-in. or more in thickness can be broken with finger 150-700 sure. Can be scratched readily by fingernail.					
		DISCONTINUIT	Y DESCRIPTION				
	Fracture	•	_	Spacing			
		Other Fractures)	(May Include Foliation or Banding)				
Description		Spacing	Description	Spacing			
Intensely frac	ctured	< 2.5 inches	Laminated	< ½-inch			
Highly fract	ured	2.5 – 8 inches	Very thin	½ − 2 inches			
Moderately fra	ctured	8 inches to 2 feet	Thin	2 inches – 1 foot			
Slightly fract	ured	2 to 6.5 feet	Medium	1 - 3 feet			
Very slightly fr	actured	> 6.5 feet	Thick	3 - 10 feet			
			Massive	> 10 feet			
		ROCK QUALITY DES	SIGNATION (RQD) 1				
	Descri	ption	RQD Va	lue (%)			
	Very	Poor	0 -	25			
	Po	or	25	- 50			
	Fa	ir	50	- 75			
	God	od	75	- 90			
	Excel	lent	90 -	100			
1 The combin	ed length of a	Il sound and intact core segments ed	qual to or greater than 4 inches in le	noth, expressed as a percer	ntage		

WEATHERING

Description

^{1.} The combined length of all sound and intact core segments equal to or greater than 4 inches in length, expressed as a percentage of the total core run length.